



# Time-projection chamber for MPD

*Stepan Vereschagin, on behalf of the  
TPC/MPD group, VBLHEP, JINR*



JOINT INSTITUTE  
FOR NUCLEAR RESEARCH



NICA


MPD

# Outline



- Nica complex, MPD experiment and TPC detector: slides 3-4
- TPC cylinders and body assembling: slides 5-7
- Read-Out Chambers and gating grid system : slides 8-9
- Gas system: slide 10
- Cooling system: slides 11-13
- Laser calibration system: slide 14
- Low voltage and High voltage power supply: slide 15
- TPC data acquisition system: slides 16-18
- TPC to MPD installation: slide 19
- TPC engineering infrastructure slide 20
- Time schedule: slide 21

# NICA Complex




For details on the NICA project look into the presentations: **“Mega-science challenges of the NICA project”** (Vladimir Kekelidze) and **“NICA accelerator complex”** (Andrey Butenko)

<https://nica.jinr.ru/>  
<http://mpd.jinr.ru/>

# TPC design requirements and main parameters



## Heavy-ion collision simulation



### The TPC/MPD design requirements:

- The overall acceptance:  $\eta < 1.2$
- The momentum resolution for charged particles is under 3% in the transverse momentum range  $0.1 < p_t < 1 \text{ GeV}/c$
- Two-track resolution is of about 1 cm
- Hadron and lepton identification by  $dE/dx$  measurements: with a resolution better than 8%
- Operation trigger rate: 7 KHz


Item	Dimension
Length of the TPC	340cm
Outer radius of vessel	140cm
Inner radius of vessel	27 cm
Outer radius of the drift volume	133cm
Inner radius of the drift volume	34cm
Length of the drift volume	170cm (of each half)
HV electrode	Membrane at the center of the TPC
Electric field strength	$\sim 140\text{V}/\text{cm}$ ;
Magnetic field strength	0.5 Tesla
Drift gas	90% Ar+10% Methane, Atmospheric pres. + 2 mbar
Gas amplification factor	$\sim 10^4$
Drift velocity	$5.45 \text{ cm}/\mu\text{s}$ ;
Drift time	$< 30\mu\text{s}$ ;
Temperature stability	$< 0.5^\circ\text{C}$
Number of readout chambers	24 (12 per each end-plate)
Segmentation in $\varphi$	$30^\circ$
Pad size	$5 \times 12\text{mm}^2$ and $5 \times 18\text{mm}^2$
Number of pads	95232
Pad raw numbers	53
Pad numbers after zero suppression	$< 10\%$
Maximal event rate	$< 7 \text{ kHz}$ ( Lum. $10^{27}$ )
Electronics shaping time	$\sim 180 \text{ ns}$ (FWHM)
Signal-to-noise ratio	30:1
Signal dynamical range	10 bits
Sampling rate	10 MHz
Sampling depth	310 time buckets



# TPC cylinders and HV electrode




TPC cylinders




Cylinders structure

C1-C2 and C3-C3 cylinders assembled




Central HV electrode






# TPC body assembling




C1-C2 and C3-C4 cylinders: **assembled**  
TPC service wheels: **assembled**  
HV membrane: **tested**  
Field Cage assembly: **July 2023**  
TPC body ready: **August 2023**



Flange





Service wheel





# The body assembling




TPC body was assembled with test rods to check TPC geometry by laser tracker AT-402 : **misalignment** between 2 flanges, HV electrode and C1-C2 cylinder - is about 0.5 mm.  
**The goal is to improve misalignment.**




# Read-Out Chambers (ROC)


Test set up for ROC certification



24 pc ROCs: **tested**




Test setup for pads calibration




- Leica MS60 - 1 second resolution
- Leica AT960 +/-10 mkm +5 mkm/m
- Leica AT403 +/-15 mkm +6 mkm/m
- Scanner AS1+AT960 +/-50 mkm

Checking pads geometry




systematic is up to 150 mkm


Full set of ROC alignment marks:



Our target is to measure coordinates of installed marks and 3968 pads in respect to the "reference hole" in each ROC.



PadPlane unflatness example



+/- 30 mkm

24 pc. of serial ROCs + 4 spare are **READY**





# Gating grid system

ROC gating grid system: test setup



Pulse rise time is  
500 ns: **OK**




<- Gate ->

<- Cathode ->

<- Anode ->

Ion drift lines

Shape of the TPC equipotentials:




Mass-production: **in progress**  
Delivery to JINR: **Sept. 2023**

# Gas system



Gas supply



TPC volume imitator

Racks


Testing is in progress

## Gas system main features:

- Drift gas mixture: 90% Ar + 10% CH<sub>4</sub> (P10);
- Insulating gas: N<sub>2</sub>;
- Operating pressure: atmospheric + 2.0 ± 0.03 mbar;
- Drift volume: 17640 liters;
- Insulating gaps volume: 2380 liters;
- Oxygen content: 20 ppm;
- Moisture content: 10 ppm;
- Recirculation rate of outer loop: 30 L/min;
- Recirculation rate of inner loop: 20 L/min







## Gases consumption:

Mode	Argon, m <sup>3</sup>	Methan, m <sup>3</sup>	Nitrogen, m <sup>3</sup>
TPC purging	84	5.4	36
Experiment:			
Per day	7.8	0.86	8.6
Per month	234	25.9	259






# Cooling system



FEE cooling plates

Bottom cooling plates




Set of top cooling plates




Cu tube Din - 3.16 mm  
Plates thickness - (4+4) mm

# Cooling prototype



Cooling simulation  
(Autodesk inventor Nastran)



Electronics water:  
T=19 C  
ROC water: T=22 C  
Air: T=23 C

Experimental and simulation  
results are compatible

T sensor based on Pt100






Air: T=23 degree (C)

Water FECs T (C)	Water ROC T(C)	SAMPAs dT (C)	FPGAs dT (C)	Pads dT (C)	ROC dT (C)	T Min (C)	T Max (C)	Comments
17	25	3÷5	7	0.27	0.6	18	33	
19	22	3÷5	7	< 0.2	0.2	20	35	optimum



# Serial cooling system



Hydraulic pressure drop for ROC chambers




Water velocity: (1.5-2.5) m/s

Systems parameters optimization by calculations – in progress



TPC system pressure with water column height



# Laser calibration system



Scheme for 1/2 TPC




Laser beam splitter



Laser beam monitor

- Number of laser "planes": 4
- Number of micro-mirrors bundles per plane: 4
- Number of beams from micro-mirrors bundle: 7
- Total number of laser "tracks" (N = 112x2): 224

micro-mirror bundles



## TPC laser calibration for electron drift velocity (root version)


Space-charge distortion in TPC volume change the electron drift velocity ( $\leq 1\text{sec.}$ )– corrections are needed.

Bychkov A.

Reasons:

- Variation in drift velocity caused by gas mixture, temperature, pressure and electric field variation.
- Radial inhomogeneities of magnetic and electric field.
- Space charge distortions due to high multiplicity in nucleus-nucleus collisions.
- TPC misalignment in the magnet and existence of the global E X B effect.

Reconstructed hits of the laser grids





## TPC electron drift velocity calibration (standalone fast version)

### Test for drift velocity correction


- Source data
  - True drift velocity = 5.5 cm/us
  - Simulated drift velocity = 5.4 cm/us
  - Test on laser grid itself
- Red — measured position
- Black — corrected position

Bychkov A.





# Low voltage and High voltage power supply



**LV&HV system based on CAEN rad. hard design:**  
*(up to 2000 Gauss and 15 kRad)*

- power converters A3486 AC/DC (380 V -> 48 V): 15+3 pc
- EASY3000 crates: 14+2 pc
- LV module - A3100B (8V/100A): 48+8 pc
- LV module - A3100HBP (14V/50A): 6+2 pc
- HV modules -A3540P (+4kV/1mA): 8+3 pc
- HV modules -A3540N (- 4kV/1mA): 2+2 pc

**Status:**


*LV+HV system: JINR-CAEN contract was signed*

*Expected delivery date to JINR: August 2023*

*test system: testing is ongoing*

**LV cables (halogen free, low smoke), S=50 mm<sup>2</sup>: was delivered**



**HV cables: was ordered**




Low voltage distribution board. Designed in INP BSU (Minsk)

# TPC data acquisition system (DAQ)


On the TPC (inside the MPD magnet)



Outside the MPD magnet



LDC computers with installed DCU cards



Ethernet 100Gbps



DAQ main parts:

Front-End-Cards (FEC): 1488 pc., 95 232 10-bit ADCs in total

Readout and Control Units (RCU): 24 pc. in total

Data Concentrator Units (DCU): 6 pc. in total

Local Data Concentrator (LDC) servers: 6 pc. in total




# Front-End Electronics




- The total number of registration channels: 64
- Maximum input charge in a linear range: 100 fC
- ADC resolution: 10 bit
- ENC: less than 1000  $e^-$
- Readout serial interface: up to 2.5 Gbps

FECs with cooling radiators




[1] J. Adolfsson, et al., SAMPA chip: the new 32 channels ASIC for the ALICE TPC and MCH upgrades, JINST 12 (04) (2017) C04008.




FECs production status:

PCBs & FECs to be ordered: 21 pc. + spare






# ReadOut Chamber DAQ test setup




Test setup at building 201, VBLHEP

RCU-64 controller testing with FEE



1. RCU prototypes
2. FECs on the ROC (62 pc. left and 31 pc. right)
3. LV power supply
4. DCU card connected with RCUs via fibers
5. Readout server




Test setup at building 40, VBLHEP





# Tooling for installation TPC to MPD

Bld. 217





MPD building





Design under optimization,  
Prototype 1:5:  
June 2023

4 units for adjustment X, Y, Z



Tooling manufacture –  
July 2023-Feb 2024  
Delivery to JINR –  
Spring 2024







# Time schedule



## TPC assembling:

Field cage assembly:	July 2023
HV tests:	August 10 2023
TPC vessel ready (glue by epoxy):	August 30 2023
Laser beams position measurements:	Sept 2023
TPC vessel tightness measurements:	Oct 2023
24 ROC chambers installation:	Nov-Dec 2023
TPC tests: laser tracks and cosmic test:	Jan-Sept 2024

## Integration TPC to MPD:

TPC racks (8pc) + cabling:	autumn 2023 - 2024
TPC rails (2pc manufacture and delivery):	Oct 30 2023

Rails installation to ECAL support structure:	Nov 2023
---	----------

## Tooling for installation TPC to MPD:

Design optimization + prototype 1:5:	June 2023
Tooling manufacture:	July 2023 - Feb 2024 (8 month)
Delivery to JINR:	Spring 2024

## TPC+ECAL cooling systems:

FE cooling:	Nov 2023
commissioning:	Sept 30 2024

## TPC installation to MPD:

## MPD commissioning:

Oct 1-Nov 30 2024
Jan 10 - Feb 2025

**Thank you for  
your attention!**