

## MPD/NICA TPC status (30.01.2020)

- TPC parameters
- TPC cylinders
- ROC chambers
- front end electronics
- gas, cooling, laser and SC systems
- cabling and tubing
- integration TPC to MPD
- time schedule


**Presented by Sergey Movchan**

**JINR team: 24 persons**


**Belarus: 6 persons**

*(INP BSU- ARTMASH: K.Afanasiev, V.Baev, Yu.Fedotova A.Litomin,  
S.Savitskiy, V.Tchekhovskiy)*

# MPD TPC parameters



Корпус TPC/ MPD




**TPC TDR – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>**

S.Movchan MPD/NICA TPC status for DAC,  
Dubna, February 04 2020

3-Feb-20


Item	Dimension
Length of the TPC	340cm
Outer radius of vessel	140cm
Inner radius of vessel	27 cm
Outer radius of the drift volume	133cm
Inner radius of the drift volume	34cm
Length of the drift volume	170cm (of each half)
HV electrode	Membrane at the center of the TPC
Electric field strength	~140V/cm;
Magnetic field strength	0.5 Tesla
Drift gas	90% Ar+10% Methane, Atmospheric pres. + 2 mbar
Gas amplification factor	$\sim 10^4$
Drift velocity	5.45 cm/ $\mu$ s;
Drift time	< 30 $\mu$ s;
Temperature stability	< 0.5°C
Number of readout chambers	24 (12 per each end-plate)
Segmentation in $\phi$	30°
Pad size	5x12mm <sup>2</sup> and 5x18mm <sup>2</sup>
Number of pads	95232
Pad raw numbers	53
Pad numbers after zero suppression	< 10%
Maximal event rate	< 7 kHz ( Lum. 10 <sup>27</sup> )
Electronics shaping time	~180 ns (FWHM)
Signal-to-noise ratio	30:1
Signal dynamical range	10 bits
Sampling rate	10 MHz
Sampling depth	310 time buckets

## ROC chamber: pad plane



2 parts

Pads capacitor  
measurement




**10 serial sets with soldered connectors - delivered Jan 2020**  
(connectivity test - in progress)

**Next (last) 15pc serial pad planes - ordered**

## TPC and ROCs: **status**




**26 pc  
ROC frames  
- in stock**



**ROC cleaning  
procedure  
- ready**



**10pc ROCs -  
tested**



**C3-C4 gluing  
- will be finished  
Feb 07 2020**



## TPC and ROCs: **summary**

### TPC assembly:

- |   |   |
|---|---|
| field cage rods (30 pc + 30 pc)           | - in manufacture                            |
| field cage mylar strips manufacture       | - Feb 2020                                  |
| flanges finishing (add holes and grooves) | - Feb 2020                                  |
| C3- C4 gluing                             | - will be finished <b>Feb 07 2020</b>       |
| C1- C2 gluing                             | - Feb 2020                                  |
| start of TPC internal structure ass.      | - Dec 2019 -> Jan 2020 -> <b>March 2020</b> |

### ROC chambers:

- |                                     |  |
|-------------------------------------|--|
| serial ROC chambers manufacture     | - in schedule ( <b>10 pc tested</b> )      |
| frames (26 pc)                      | - ready                                    |
| serial pad planes (20 pc ready)     | - last 15pc ordered                        |
| HV for ROC gate electrode           | - design started, in progress              |
| test chamber with 2048ch r/o system | - Sept 2019 -> Nov 2019 -> <b>Feb 2020</b> |

TPC transportation platform and manipulator for ROC chamber installation - **ready**

# TPC electronics requirements

## Data rates:

- trigger mode – **20 GByte/sec** ( $N=1000$  tracks)
- continuous readout mode - **300 GByte/sec**

## Particle fluence for $R=35$ cm & 10 years (Oct 2019 update):

- neutrons + protons –  **$10^{**11}$  p/cm<sup>2</sup> per year**
- e- & e+ ions –  **$2 \times 10^{**10}$  p/cm<sup>2</sup> per year**
- **$10^{**5}$  p/cm<sup>2</sup> per year**

## Dose:

Expected dose - **2 kRad per 10 years**

*SAMPA v3/v4 tested at:*

*proton fluence - up to  $N=10^{**12}$  per cm<sup>2</sup>*

*ion fluence - up to  $N=10^{**7}$  per cm<sup>2</sup> & LET=(3-125) MeV cm<sup>2</sup>/mg*

*T chip=(45-85) degree =>*

*SEL =  $1 \times 10^{-7}$  cm<sup>2</sup> for LET=16 MeV cm<sup>2</sup>/mg*

*TID and SEL - ok!*

*FPGA Cyclon V (technology -130 nm): 28 nm):*

*TID – up to 100 kRad, SEL < 0.5 sec for LET=26.6 MeV cm<sup>2</sup>/mg*

*TID – ok!, SEL – no so good*

# TPC electronics: FE cards




Top view (service side)

- Double-board FEC provides opportunities for possible upgrade of the card readout.
- Transfer of data and trigger signals was realized with the same high-speed serial interface.
- 16 values of currents, voltages and board temperatures are controlled with ADC.
- External circuit and embedded protection functionality against SEU are provided.
- Remote system update for FEC firmware was provided.


- The total number of registration channels: 64
- Input signal dynam. range: 100 fC
- ADC resolution: 10 bit
- ENC: less than 1000e<sup>-</sup>
- SAMPA chips configured and controlled via FPGA
- Readout serial interface: up to 2.5 Gbps



Bottom view (ROC side)



## FEC slow control data



**T<sub>SAMPA</sub> = 57 degree**  
**T<sub>FPGA</sub> = 54 degree**  
**Board LV: 1.7V & 1.1V**  
**SAMPA (2 pc): 1.25V/500 mA**  
**FPGA: 1.1V/10 mA (stand by mode)**


**Status: in progress**

# TPC electronics: status

**SAMPA chips (4500 pc) delivered to JINR - June 2019**

## Pilot system – 512 ch



Eight cards pilot system



- 1) Trigger, clock, reset distr. board .
- 2) System controller.
- 3) 64-ch SAMPA- FEC.
- 4) HSSI (up to 2.5 GBps; up to 8 FECs).
- 5) Data/conf. full duplex HSSI port; clock 40 MHz, trigger, reset.

**tests with FPGA  
Arria 10 – in progress**


**Status: tested**





# TPC electronics: status and schedule

## Test bench




Front view

1) 32 FECs; 2) RCU prototype;  
3) DCU module; 4) LV power  
supply; 5) Optical link.

Item	Date	
Testing 512-channel system (FEC v1.0) finished	Jan. 2019	✓
Testing 256-channel system (FEC v2.0) finished	Feb. 2019	✓
Preproduction version FEC PCBs sent for fabrication	Mar. 2019	✓
Half-ROC readout system base design finished	Mar. 2019	✓
Receive SAMPA V4 chips at Dubna	Jul. 2019	✓
34 preproduction version FEC assembled and tested	Nov. 2019	✓
32 preprod. version FEC installed on Pilot 2048 ch. Syst.	Dec. 2019	✓
Instrumented Half ROC system testing	Feb. 2020	
Testing instrumented ROC finished	Apr. 2020	
Production version FEC PCBs ready	May 2020	
1st batch of prod.ver FEC (130 pcs ) fabricated	Jul. 2020	
2nd batch of prod.ver FEC (800 pcs ) fabricated	Sept. 2020	
3rd batch of prod.ver FEC (800 pcs ) fabricated	Dec. 2020	

# TPC electronics: FE cards integration and cooling



2 radiators (narrow and wide)  
FE cards – no individual cooling

Status: **in progress**

## INP BSU (Minsk): TPC LV system

LVDB mass-production (60 pc) - done **Ok!**

LV system based on CAEN rad. hard design:

(up to 2000 Gauss and 15 kRad)

- power converters A3486 AC/DC (380 V  $\rightarrow$  48 V)
- CAEN EASY3000 system
- LV module - A3100B (2÷7V/100A)

Status:

- test system – ordered, delivery time – May 2020
- invoice for full system - got, delivery time – (270÷300) days

LV cables (halogen free, low smoke):

S=50 mm<sup>2</sup> – delivered to JINR **Dec 2019**

S=120 mm<sup>2</sup> – delivered to JINR **Dec 2019**

**in progress ...**

Team for cabling – **looking ...**



# TPC gas system


Gas supply



Status - commissioning  
in progress

Racks

TPC volume  
imitator






Status - commissioned (Bld.217)

paper flow - in progress ...




# TPC cooling system





**Barrel part – shorter and fixed to TPC**

## TPC **cooling** system: tubes layout and set of thermal panel prototypes



Service wheel



Tubes layout prototyping

Status - **in progress**




Al plate – **2x1 mm**  
Al tube - **D=8/6 mm**




# TPC laser calibration system

$\frac{1}{2}$  TPC




micro-mirror  
bundles





Laser “planes” – 4+4  
Points per plane – 4  
Beams per point – 7  
Laser “tracks”, **N - 224**

# TPC laser calibration system







Semi transparency mirror & prism



- full set of micro-mirror bundles - **assembled**
- 2 lasers (special option) – **commissioned**
- laser beam splitter - **delivered to JINR**
- laser beam monitors - **prototype under tests**



# TPC laser calibration system: laser beams layout



**laser beam layout – under finalization**

# TPC slow control : sub-systems status

## LV system:

- 1) **CAEN EASY3000** (crate SY4527 (2pc), crate EASY3000 (12pc), module A3486 AC/DC (400V) converter (13pc), module PS A3100B (55pc) + **software GECO 2020 - ok!**
- 2) **Custom made stabilizers** (module LVN9 (48pc-**ok**)) + crate 6U (1pc), custom control units (12pc) + crate controller (1pc)+ PC) + **custom software – prototype tests in progress**

## HV system:

- 1) **MWPC: CAEN** (crate SY4527-2pc + modules A7236DN -3.5kV/1.5mA, A7236DP +3.5kV/1.5mA, A1542HDN -500V/1mA ) + **software GECO 2020 - ok!**
- 2) **TPC HV electrode (- 30 kV): Iseg HV PS + Iseg software – ordering**
- 3) **HV for ROC gate: custom made system** (crate – 2pc, modules –24pc, crate controller- 2pc) + **custom software - NO**

## DAQ:

**Hardware:** FEC64 (1488pc), ROC controller (24pc), data server (24pc) + **TPC team firmware and software – in progress**

**Trigger ???...**

**Synchronization ??? ...**

**Clock ??? ...**

# TPC slow control : SC

## Gas system:

**Hardware:** DAQ32 module + custom software + PC (PNPI, Gatchina) – **ok!**



## Cooling system:

**Hardware:** NI (national instruments (crate + ADCs) + 75 channels for hitters control + thermo sensors (100pc)) + **custom software - started**

## Laser system:

**Hardware:** PC (1pc), industrial PC (2pc), controllers (2pc), cooling system (2pc), UV laser (2pc), synchronization module (1pc) + **laser producer software – not started yet**





## TPC: cables and tubes integration



**Optimization - in progress**



## TPC: trays



in progress ...

# TPC services: status

## LV system:

- serial LVDB (60 pc) – **delivered** to JINR
- serial LVDB cooling plate – **delivered** to JINR
- CAEN EASY3000 LV system - test system ordered, full system - invoice got
- LV power cables – **delivered** to JINR
- patch-panels - under discussion

## HV system:

- CAEN EASY3000 HV system - invoice got
- HV cables - will be ordered, delivery **June 2020**

## Gas system:

- equipment - **commissioned**
- commissioning of cryogenic vessels for Ar and N2 - paper flow in progress

## Cooling system:

- FE cooling prototypes – ordered, one manufactured
- testes and measurements with prototype – in progress
- barrel and end cap thermal panels (full set) – **delivered**
- service wheel cooling tubes routine optimization - in progress
- FE cooling radiators mass-production - **Sept 2020**

## TPC services: **status** (continue)

### Laser calibration system:

- |                                       |  |
|---------------------------------------|--|
| lasers (2 pc)                         | - <b>commissioned</b>                        |
| laser beam splitter                   | - <b>delivered</b>                           |
| beam monitors (WEB cameras + optics ) | - prototype tests, <b>design in progress</b> |
| channels for laser beams inside MPD   | - under finalization                         |

### Slow control system (software):

- LV system – more less ok!
- HV system – more less ok!
- HV for ROC gate – **on critical path**
- DAQ – in progress
- Gas system – ok!
- Cooling system – **started**
- Laser system – **not started yet**

## TPC services: **status** (continue)

### INTEGRATION:

TPC sub-systems integration	- in good shape
list of TPC cables and pipes	– <b>updated</b>
electronics platform (TPC racks)	- <b>started</b>
trays (cables and pipes)	- <b>started</b>

Integration TPC into MPD – **not started yet**  
(**waiting for final ECAL design** and start sub-detectors integration to MPD)

Tooling for installation TPC into MPD - **not started yet**






# Time schedule

update - 15.04.2019


TPC time schedule



\* Current version of TPC dimensions was approved of 31.01.2013

 development  
 production and test  
 finished/commissioned, milestone

# Thank you for attention!



<http://nica.jinr.ru/>  
<http://mpd.jinr.ru/>

**TDR TPC – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>**




**SPARE**




## ROC chamber: test results



ROC-14, Ar/CH<sub>4</sub> (90/10), dark current



ROC-14, X-ray line scan, step 3 mm,  
Ar/CH<sub>4</sub> (90/10),  $U_a = 1,45$  kV,  $U_{drift} = -1120$  V,  
**uniformity 18,4%**





**Fe-55: FWHM ~ 20%**

### Test procedure:

- counting plateau
- dark current
- energy resolution (Fe-55)
- uniformity of gas gain
  - ✓ linear scan
  - ✓ area scan



# ROC chamber: test SAMPA chip with ROC chamber




ROC-chamber tested with SAMPA chip (HV=+1450 V):

**ENC = 828 e-** (for small pads), **ENC = 869 e-** (for big pads)  
(20% more than expected due to digital noise)

Waiting for 30 FE boards with read out system for tests with ROC

# TPC gas system





Gas mixture	Ar + 10%CH <sub>4</sub>
TPC gas flow, nominal	200 l/min
TPC overpressure	(2.0 ± 0.1)mBar
O <sub>2</sub> admixture	20 ppm
H <sub>2</sub> O admixture	10 ppm
External loop, refresh gas rate	30 l/min
Fresh part of gas mixture add to external loop, range	(0-50) l/min
TPC isolating gas	N <sub>2</sub>
N <sub>2</sub> gas flow	(5-20) l/min

**Delivery to JINR:**

gas supply system - 2015

purification system - 2017

# TPC: transportation platform and ROC manipulator



**LHEP, bld. 205 – stored at JINR**

