


# MPD/NICA TPC status (23.04.2020)


- TPC parameters
- ROC chambers
- TPC assembly
- front end electronics
- gas, cooling, laser and SC systems
- cabling and piping
- integration TPC to MPD
- time schedule




Presented by Sergey Movchan

JINR team:      **24 persons**  
Belarus:          **6 persons**

# MPD TPC parameters



Корпус ТРС/ МПД



TPC TDR – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>

22-Apr-20

S.Movchan MPD TPC status, Dubna, Russia, April  
23 2020


Item	Dimension
Length of the TPC	340cm
Outer radius of vessel	140cm
Inner radius of vessel	27 cm
Outer radius of the drift volume	133cm
Inner radius of the drift volume	34cm
Length of the drift volume	170cm (of each half)
HV electrode	Membrane at the center of the TPC
Electric field strength	~140V/cm;
Magnetic field strength	0.5 Tesla
Drift gas	90% Ar+10% Methane, Atmospheric pres. + 2 mbar
Gas amplification factor	~ $10^4$
Drift velocity	5.45 cm/ $\mu$ s;
Drift time	< 30 $\mu$ s;
Temperature stability	< 0.5°C
Number of readout chambers	24 (12 per each end-plate)
Segmentation in $\phi$	30°
Pad size	5x12mm <sup>2</sup> and 5x18mm <sup>2</sup>
Number of pads	95232
Pad raw numbers	53
Pad numbers after zero suppression	< 10%
Maximal event rate	< 7 kHz (Lum. $10^{27}$ )
Electronics shaping time	~180 ns (FWHM)
Signal-to-noise ratio	30:1
Signal dynamical range	10 bits
Sampling rate	10 MHz
Sampling depth	310 time buckets

# ROC chamber: pad plane

ROC chamber assembly hall (Bld.40)



2 parts



Connectivity  
test




Next 10 serial pad planes with soldered connectors:  
delivered - Jan 2020  
connectivity test - ok!

Next (last) 15pc serial pad planes - ordered


# ROC chambers status




26 pc  
ROC frames  
- in stock



ROC cleaning  
procedure






14 pc ROCs -  
tested



Wire pitch check  
set up

## TPC assembly (Bld.217) – common view



ISO-6

$S=84 \text{ m}^2$


# TPC and ROCs: summary

## ROC chambers:

- serial ROC chambers manufacture
- frames (26 pc)
- serial pad planes
- HV for ROC gate mesh
- test chamber with 2048ch r/o system
- in schedule (14 pc tested)
- ready
- last 15 pc ordered, ok!
- design started ... **on critical path**
- ready for tests**

## TPC assembly:

- C3- C4 gluing
- C1- C2 gluing
- field cage rods (30 pc + 30 pc)
- field cage mylar strips manufacture
- flanges finishing (add holes and grooves)
- start of TPC internal structure ass.
- done (Feb 18 2020)
- Mach 2020 → **May 2020 ?**
- manufactured
- March 2020-> **May-June 2020 ?**
- March 2020 -> **May-June 2020 ?**
- March 2020 -> **Lune 2020 ?**



TPC transportation platform and manipulator for ROC chamber installation - **ready**

# TPC electronics requirements

## Data rates:

- trigger mode – **20 GByte/sec ( $N=1000$  tracks)**
- continuous readout mode - **300 GByte/sec**

## Particle fluence for $R=35$ cm & 10 years (October 2019 update):

- neutrons + protons –  **$10^{11}$  p/cm<sup>2</sup> per year**
- e- & e+ –  **$2 \times 10^{10}$  p/cm<sup>2</sup> per year**
- ions –  **$10^5$  p/cm<sup>2</sup> per year**

## Dose:

Expected dose - **2 kRad per 10 years**


SAMPA v3/v4 tested at:  
proton fluence - up to  $N=10^{12}$  per cm<sup>2</sup>  
ion fluence - up to  $N=10^7$  per cm<sup>2</sup> & LET=(3-125) MeV cm<sup>2</sup>/mg  
 $T_{chip}=(45-85)$  degree =>  
 $SEL = 1 \times 10^{-7}$  cm<sup>2</sup> for LET=16 MeV cm<sup>2</sup>/mg

**TID and SEL - ok!**


FPGA Cyclon V (technology -130 nm): 28 nm):  
TID – up to 100 kRad, SEL < 0.5 sec for LET=26.6 MeV cm<sup>2</sup>/mg

**TID - ok!, SEL - no so good**


# TPC electronics: block diagram of one chamber readout



## SAMPA chip



**RCU and data concentrator based on commercial kits**



# TPC electronics: FE cards



Top view (service side)



- The total number of registration channels: 64
- Input signal dynam. range: 100 fC
- ADC resolution: 10 bit
- ENC: less than  $1000 e^-$
- SAMPA chips configured and controlled via FPGA
- Readout serial interface: up to 2.5 Gbps



Bottom view (ROC side)

- Double-board FEC provides opportunities for possible upgrade of the card readout.
- Transfer of data and trigger signals was realized with the same high-speed serial interface.
- 16 values of currents, voltages and board temperatures are controlled with ADC.
- External circuit and embedded protection functionality against SEU are provided.
- Remote system update for FEC firmware was provided.

## FEC slow control data




**ENC ~ 0.8 ADC  
(~ 500 e-)**

**SAMPA chips (4500 pc)  
delivered to JINR  
- June 2019**

# TPC electronics: status and schedule

## Bench test



Front view

- 1) 32 FECs; 2) RCU prototype;
- 3) DCU module; 4) LV power supply; 5) Optical link.


Item	Date
Testing 512-channel system (FEC v1.0) finished	Jan. 2019 ✓
Testing 256-channel system (FEC v2.0) finished	Feb. 2019 ✓
Preproduction version FEC PCBs sent for fabrication	Mar. 2019 ✓
Half-ROC readout system base design finished	Mar. 2019 ✓
Receive SAMPA V4 chips at Dubna	Jul. 2019 ✓
34 preproduction version FEC assembled and tested	Nov. 2019 ✓
32 preprod. version FEC installed on Pilot 2048 ch. Syst.	Dec. 2019 ✓
Instrumented Half ROC system testing	Feb. 2020
Testing instrumented ROC finished	Apr. 2020
Production version FEC PCBs ready	May 2020
1st batch of prod.ver FEC (130 pcs ) fabricated	Jul. 2020
2nd batch of prod.ver FEC (800 pcs ) fabricated	Sept. 2020
3rd batch of prod.ver FEC (800 pcs ) fabricated	Dec. 2020

Test ROC with FE (2048ch) –> **May 2020 ?**

# Data concentrator ASIC (NRNU MEPhI)

65 nm CMOS process, Mixed-Signal, Low Power

Bi-directional interface, readout from 2 SAMPA chips (2.56 Gb/s speed, trigger mode, rad-tolerant)



# TPC LV+HV system


LV&HVsystem based on CAEN rad. hard design:

(up to 2000 Gauss and 15 kRad)

- power converters A3486 AC/DC (380 V -> 48 V) – 13 pc
- EASY3000 crates – 12 pc
- LV module - A3100B (2÷7V/100A) – 55 pc

Status:

- test system – ordered
- quotation for full TPC LV+HV system got, procurement – in progress



LV cables (halogen free, low smoke):

S=50 mm<sup>2</sup> – delivered to JINR Dec 2019

S=120 mm<sup>2</sup> – delivered to JINR Dec 2019

HV cables - will be delivered July 2020



LVDB boards (60 pc) - delivered

*INP BSU (Minsk)*


Team for cabling and piping – looking ...

# TPC gas system

Gas supply






Commissioning -  
in progress




Status - commissioned (Bld.217)

# TPC cooling system



**Barrel part – shorter and fixed to TPC instead TOF structure**



# TPC cooling system: pipes layout and thermal panels



Service wheels -  
manufactured



Pipes layout  
optimization



Prototypes:




All serial thermal panels –  
manufactured

# TPC: FE cooling - prototype 1, INP BSU Minsk

Set up

FE power stabilization board



ROC + FE



Water  
Al tube, Din  
Flow  
CAEN  
(+3.5V/28.2A, +4/2V/22.0A)

FE power (31pc) - 134.9 W  
Thermal pad - 0.8 W/m\*K  
Al plates thickness -(11+11) MM

Results:

SAMPA chips - (22-25) deg  
FPGA chips - (28-33) deg  
FE PS cables - 5.1 W


Disadvantages:

Radiation length - 25%  
Impossible to do replacement  
of FE cards



=> New prototype (№2)

# TPC: FE cooling - prototype 2, INP BSU Minsk

## Set up



## Test sample



Water  
Cu tube Din  
Flow

- +15 degree  
- 3.36 mm  
- (0.3-6) l/min

FE power (1pc) - 5.2 W  
Thermal glue - 6 W/m\*K  
Plates thickness - (4+4) MM

## Results:

FPGA chip - 28 deg (6 l/min)  
- 40 deg (0.3 l/min)  
- 70 deg (no water flow)

## Advantages:

Radiation length - 9%  
Easy FE cards replacement

=> Prototype №3

# TPC: FE cooling - prototype 3, INP BSU Minsk

*combination of proto 1+proto 2*

## Bottom cooling plates



## Set of top cooling plates






Cu tube Din - 3.36 mm  
Plates thickness - (4+4) MM



Tests – May 2020 ?

# TPC laser calibration system: laser beams layout



Laser "planes"

- 4

Micro-mirrors bundles per plane

- 4

Beams from micro-mirrors bundle


- 7

Laser "tracks", N


- 224

**laser beams layout –  
under finalization**



# TPC laser calibration system



Short periscope scheme




## Optical table schemes




- optical table with components (2pc) – ordering
- short periscope (2pc) – ordering


# TPC laser calibration system



Semi transparent mirror & prism



ordered



- full set of micro-mirror bundles - assembled
- 2 lasers – commissioned
- laser beam splitter – ready to install
- laser beam monitors – prototype under tests

# TPC slow control system: sub-systems status

## LV system:

- 1) CAEN EASY3000 (crate SY5527 (1pc), crate EASY3000 (12pc), module A3486 AC/DC (400V) converter (13pc), module PS A3100B (55pc) + software **GECO 2020 - ok!**
- 2) Custom made power stabilizers (module LVN9 (60pc-ok)) + crate 6U (1pc), custom control units (12pc) + crate controller (1pc)+ PC + custom software) - **in progress**

## HV system:

- 1) MWPC -> CAEN crate EASY3000 + modules A3535P/N 3.2kV/0.5mA – 6pc - **ok!**  
Spare option: CAEN crate SY4527-2pc + modules A7236DN -3.5kV/1.5mA, A7236DP +3.5kV/1.5mA, A1542HDN -500V/1mA + software **GECO 2020 - ok!**
- 2) TPC HV electrode (- 30 kV): Iseg HV PS - **ask quotation**
- 3) HV for ROC gate: custom made system (crate – 2pc, modules –24pc, crate controller- 2pc + custom software) – **on critical path**

## DAQ:

**Hardware:** FEC64 (1488pc), ROC controller (24pc), data server (6pc) + **TPC team firmware and software – in progress**



## TPC slow control system: sub-systems status

### Gas system:

**Hardware:** DAQ32 module + PC (PNPI, Gatchina) + **custom software – ok!**

### Cooling system:

**Hardware:** NI (National Instruments (crate + ADCs) + 75 channels for hitters control + thermal sensors (100pc)) – **ok!, custom software - started**


### Laser system:

**Hardware:** PC (1pc), industrial PC (2pc), controllers (2pc), cooling system (2pc), UV laser (2pc) – **ok!** synchronization module (1pc) and **custom software – design and software not started yet**






### Trigger and synchronization – **no info**

### Integration SC sub-systems to common TPC slow control system – **not started yet**

# TPC: cables and pipes integration




Trays layout concept




Optimization - in progress

# ITS+FFD integration to TPC



TPC



FFD




ITS



“Tube” for  
FFD+ITS

Concept – done, design - in progress



# MPD TPC status 2020: summary



## Status:

### • TPC:

- vessel (C3-C4 cylinders)
- TPC internal structure assembly
- ROC chambers (24pc)

- assembled
- March 2020 → **start of June 2020**
- 14 pc tested, 2 pc in manufacture  
next 15 pc pad planes - ordered

### • Electronics:

- FE electronics (next 32 cards)
- RCU controller
- FE (32 cards) + ROC tests
- FE cooling prototype 1
- FE cards mass-production and tests
- FE radiators mass-production

- ordered
- design in progress
- March 2020 → **May 2020 ?**
- designed, manufactured, tested -> **re-design done** (prototype 2)
- **July-Dec 2020 -> 2021**
- Sept 2020

### • Sub-systems:

local TPC DAQ

- in progress

Gas system

- commissioned, integration to MPD started

Cooling system: full set of thermal screen panels - delivered, FE cooling and system design - in progress

HV+LV systems

- procurement started (CAEN)

Laser calibration system: UV lasers and laser beam distrib. systems - delivered, rest parts - ordered

Slow control system

- sub-systems more less ok, integration to common SC system **not started yet**

### • Cabling and piping:

TPC cabling and piping

- in progress

MPD TPC trays filling

- in progress

### • Integration TPC to MPD

TPC racks (5 pc) layout

- in progress

tooling for installation TPC to MPD


- in progress

### • TPC schedule

start of TPC commissioning

- **beginning of 2021**

MPD event display - <http://db-nica2.jinr.ru/> (V.Krilov) running on smart phone too ...



Example  
for TPC

<http://nica.jinr.ru/>  
<http://mpd.jinr.ru/>

TPC TDR – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>

# Thank you for attention!