## DAQ hardware

## Near detector

Mechanics:

- 374 Front End Concentrators VME 6U double width 12 inputs, 1 outputs
- 43 VME crates,  $0.5kW \rightarrow 9-10$  racks
- Option with ATCA crates < 20

Cables:

- From detectors to DAQ: 4436 optic links
- From DAQ to control room: 374 optic links (double), max 480 links
- For singe fiber cables full diameter about 200mm
- For a multi-fiber cables (12,24) full diameter about 160mm

## In barrack

3 VME crates (1kW) 20 DAQ computers (1kW)  $\rightarrow$  3-4 racks

