




Upgrade of the BM@N detectors




Anna Maksymchuk on behalf of the BM@N Collaboration
19/04/2021

BM@N Experimental Setup



Beam pipe before the target


S.Piyadin, A.Kubankin



Four stainless steel vacuum boxes downstream the target are replaced by aluminum ones. The design and production of the target station control system and pneumatic actuator mechanics is performed by A.Kubankin group. Works to be finished by June 2021.

Trigger system. Changes in general scheme.

Trigger and DAQ groups



Part A
(managed by the trigger group):

generates physics triggers;

Fragment Detector (FD) and FHCAL (ZDC) are added to trigger detectors.

Part B
(managed by the DAQ group):


makes downscaling of the physics triggers (up to 16 triggers can be provided);

makes Before/After protection;

generates special triggers.


Trigger system. Status of beam counters

Trigger group



Design of BC1/VC
PMT mount

Sketch of vacuum box
for BC1 and VC



Design of BC2
PMT base and FEE

Sketch of vacuum
box for BC2

BC1 and VC Status and plans:


- Vacuum components **ready**
- PMT Hamamatsu R2490-07 **available**
- PMT sockets ordered, **exp. May 2021**
- PMT voltage dividers production, **June-July 2021**
- Scintillators $100 \times 100 \times 0.25 \text{ mm}^3$ (BC1) and $\text{Ø}100 \times 10 \text{ mm}$, hole $\text{Ø}27 \text{ mm}$ (VC) **available**
- Scintillator mount design **in progress**

BC2 Status and plans:

- Vacuum components **ready**
- MCP-PMT XPM85112/A1-Q400 (Photonis) **available**
- PMT base and FEE parts, **produced and delivered**
- PMT assembly and testing, **May-June 2021**
- Scintillators BC400B $30 \times 30 \times 0.15 \text{ mm}^3$ **available**
- Scintillator mount design **in progress**

Trigger system. Upgrade of T0U module

Trigger group



T0U Module Functionality:

- Implements trigger logic in FPGA
- Accepts or provides I/O analog, NIM, TTL signals via cards 4
- Accepts LVDS signals via HDMI connectors 2
- Provides LV to FEE (cards 3, HDMI connectors 2)
- Forms input signals to TDC (Molex connectors 1)


Points of upgrade:

- Improved input boards with discriminators (16 inputs)
- Additional I/O boards TTL (LEMO), up to 24 channels (e.g., can be used for output signals to scalers)
- New power converter, capable to drive extended set of I/O cards
- Second USB 2.0 port + 2 optical links

Status and plans:

- All parts are produced and delivered
- Assembly and testing May-July 2021



Design and produced parts of upgraded T0U



Trigger system. Multiplicity detectors

Trigger group


Barrel Detector upgrade:



- New (with lower noise) FEE board;
- the board is **produced and delivered**,
- the old one will be replaced **Jun.-Aug.2021**
- Inner cylindrical Pb shield (5 mm thick, 10 cm long)
- Outer Pb shield (R=50cm, 1cm thick)


FSD group

Multiplicity detector upgrade




- **detector:** Silicon single-sided Detector, 525 μm thickness, 8 strips located at an angle with an interval of 5.63° and is an isosceles trapezoid in shape (45°) and active area 30.8 cm^2 (5 times bigger than previous Si-multiplicity trigger 2018).
- **mechanical design :** new design is based on 2 symmetric half-planes (inner diameter $\text{Ø}52 \text{ mm}$), which simplify multiplicity trigger assembling process around installed beam pipe. Multiplicity trigger is located at 62 mm downstream the target.
- **FEE:** based on 32 channel IC-AST-1-1 (Minsk) with adjustable threshold.
- **current status:** two half-planes assembled and tested with previous FEE (2018). New FEE design with new gain parameters is under discussion (due to strip capacitance 5 times increase).

Forward Silicon and beam detectors




Beam
profilometer x2



Beam tracker
x3

Target



Multiplicity
trigger



Forward Silicon
Detector x3


Direction of Ion Beam





See talk by B.Topko

Beam profilometer and beam tracker

FSD group



- **detector:** DSSD, 32×32 strips, pitch p+ / n+ strips 1.8 mm, thickness 175 μm , active area 60 × 60 mm^2 ;
- **mechanical design:** The mechanical construction supports automatic removal of profilometer planes from beam zone to special branch pipe after beam tuning;
- **FEE:** for light ions based on **VA163 + TA32cg2 (32 ch, dynamic range: -750fC ÷ +750fC)**;
- **current status:** two vacuum stations with flanges and cable connectors are ready, Silicon Detectors assembled on PCBs and tested with alpha-source (5.5 MeV), (**FEE+ADC+DAQ**) design in progress within schedule.





- **detector:** DSSD, 128×128 strips, pitch p+ / n+ strips 0.47 mm, thickness 175 μm , active area 61×61 mm^2 ;
- **FEE:** based on **VATA64HDR16.2 (64 ch, dynamic range: -20 pC ÷ +50 pC)**;
- **current status:** three vacuum stations with flanges and cable connectors are ready, Silicon Detectors assembled on PCBs and tested with alpha-source (5.5 MeV). Cross-board and FEE PCB are under test. Mechanical support and FEE cooling in progress within schedule.

Forward Silicon detectors



Upper half-plane without EM + light shielding (5 modules)




- **Detector:** DSSD, 640×614 strips, pitch p+ / n+ strips $95/103 \mu\text{m}$, thickness $300 \mu\text{m}$, stereo angle between strips: 2.5° , active area $63 \times 63 \text{ mm}^2$;
- **FEE:** based on VATAGP7.1 (128 ch., dynamic range: $\pm 30\text{fC}$). 5 ASIC per PCB.
- **Current status:** all 84 FEE PCB fully assembled (100%), 38 from 84 FEE PCB are tested (45%), 12 from 42 FSD Si modules fully assembled (29%), 10 from 42 FSD Si modules are tested (24 %), FSD half-plane assembly has started.

STS group

BM@N STS



BM@N STS Station



BM@N STS Ladder



BM@N STS Module

Four stations are based on CBM-type modules with double-sided microstrip silicon sensors:


- Pitch 58 μ
- Stereo angle 7.5°
- Thickness 300 μ
- Sizes: 62x62, 62x42 mm²

Number of modules: 292
Number of channels: ~600k
Number of ladders: 34


Customized electrical test setup used through the assembly process




Custom-designed jigs for the assembly of BM@N modules



BM@N STS



Mechanical testing of flexible cables during assembly



Custom-designed mechanical parts for the Front-end board

Key milestones of the BM@N STS project

1. *Technical Design Review (100%)*
2. *R@D of the model and supermodel (the ladder) components EDR(90%)*
3. *Technology for module assembly including step-by- step QA control (90%)*
4. *Technology for ladder assembly (75%) endurance and long time testing*
5. *Mainframe mechanics (25%)*
6. *Liquid cooling - choice between water and freon (10%)*
7. *Gas cooling for temperature stabilization (?)*
8. *DCS with WinCC OA (5%)*
9. *Infrastructure extension (50%)*
10. *Readout electronics (?)*

See talk by Yu.Murin

- 2023 – pilot v. of STS based on two stations with 42 modules
- 2023-2024 – expansion of the system to 292 modules *provided priority given to BM@N STS and not CBM STS*


GEM central tracking system

Cosmic stand for long-term GEM tests


GEM group

Goal: quality “passport” for every module.


Left r/o, right r/o and hot-zones are treated as independent parts




2D occupancy plot



Spatial response uniformity



Spatial efficiency





First stage – tests of $1632 \times 390 \text{ mm}^2$ detectors (finished, data is under analysis)

Second stage – tests of $1632 \times 450 \text{ mm}^2$ detectors (05-06/2021)

GEM central tracking system

GEM support mechanics inside the SP-41 magnet




Status and plans:

- 13 GEM detectors are assembled and pass long-term quality tests at cosmic test-bench;
- 1 defected GEM detector is shipped to CERN for repair;
- 2 spare detectors are planned to be assembled at CERN at summer 2021 (all parts are ready);
- Data on spatial efficiency, resolution and response uniformity is under analysis;
- Development of the mechanics design for GEM planes precise installation inside the magnet was done by “Pelcom” (Dubna)- finished;
- Production of the mechanics is currently performed by “Pelcom” (Dubna) – deadline 09.2021;
- Material budget of the GEM central tracking system full configuration together with mechanics for heavy ion runs is estimated;
- Gas control system is under construction, all components are ordered;
- New fast electronics is planned to be integrated after 2022. Kintex7 based 128ch GEM evaluation board was designed and produced by DAQ group for VMM3a tests.

Forward Si+ STS +Gem configuration


Four configurations of the tracking detectors are foreseen:

- Forward Si + 7 GEMs: beam intensity few 10^5 Hz , 2022
- Forward Si + “pilot” STS station + 7 GEMs: beam intensity few 10^5 Hz , 2023
- Forward Si + 4 STS stations + 7 GEMs: beam intensity few 10^5 Hz, after 2023
- 4 STS stations + 7 GEMs (fast FEE): high beam intensity few 10^6 Hz, after 2023-



Configuration without STS (2022)


2023 year – “pilot” configuration
After 2023 year – full configuration



Configuration with STS

Forward Si will be removed after integration of STS full configuration into BM@N setup (after 2023 year, high beam intensity - few 10^6 Hz)

Hybrid central tracker STS+GEM momentum resolution for different magnetic field values



Beam pipe inside the SP-41 magnet

S. Piyadin, V. Spaskov, A. Kubankin




1 meter prototype of the BM@N carbon beam pipe (DD “Arkhipov”)

Experimental setup for X-ray tests


First vacuum tests were done at LHEP JINR (Spring 2020). Tests have shown an insignificant leakage level of side surfaces of the sample, vacuum up to 10^{-5} .

Tests of the sample with X-ray radiation are performed by A. Kubankin group (Belgorod University) to check the carbon layer thickness. The achieved accuracy of the wall thickness measurement: better than 10 μm for the time of measurement 10 seconds (one point).




X-ray 3D map of the wall thickness distribution


Beam pipe inside the SP-41 magnet



BM@N carbon beam pipe configuration (Au 3.8 AGeV 1800 A ~ 0.9 Tl)



Design of the non-flange connections




Design of the support system, which uses the surface of GEMs

KB “Arkhipov” (Moscow, Russia) was selected through a tender procedure for the beam pipe manufacture. First stage of the contract: Development of the 3D models of the beam pipe, non-flange connectors, production and assembly equipment, calculation of the strength characteristics of 3D model nodes. Second stage: Production of the beam pipe and non-flange connectors (June 2021).

Design and tests of the carbon vacuum beam pipe


Faculty of Mechanical Engineering of the Czech Technical University
Nuclear physics institute, The Czech Academy of Sciences

Test of vacuum compatibility



Test of material and vacuum stability under proton beam



Radiation hardness test




The test was performed September 3, 2020

The sample behaved stably during the testing

Updated design of the pipe connectors



- The critical apex angle ϑ of the cone was found by testing
- To achieve a vacuum-tight cone, the apex angle must be 20° or less
- $\vartheta \leq 20^\circ$




1065x1065 mm² and 2190x1453 mm² CSC chambers



Cosmic stand for the 1065x1065 mm² CSC

Status and plans:

- One CSC 1065x1065 mm² is produced and tested at Nuclotron beam;
- Assembly of the three 1065x1065 mm² chambers is finished.
- Tests of the assembled chambers with r/a source and cosmic rays are to be performed by the end of summer 2021.





Cathode planes of the 2190x1453 mm² CSC

Status and plans:



- Cathode planes and honeycomb panels are delivered to JINR;
- Assembly and tests of the first 2190x1453 mm² CSC chamber – 03.2022;
- Assembly and tests of the second 2190x1453 mm² CSC chamber – middle 2022;

Status of ToF-400 & ToF-700



Both time-of-flight systems are ready for the heavy ion beam program



Preliminary result of identification, GEM+CSC track extrapolated to ToF-400



Preliminary result of identification, GEM+DCH track extrapolated to ToF-700



ECAL status

- two racks for ECAL in the magnet are assembled
- tests of array of modules for second arm of the ECAL are performed



Location of ECAL in the magnet
SP-41



New racks for ECAL



Cosmic tests of the modules





New mechanics for the two-arm
calorimeter is ready



The ADC and modules for the two arms ECAL have been
prepared.



Status of new FHCaI



20 PSD CBM nodules - transverse size $20 \times 20 \text{ cm}^2$, 5.6 nuclear interaction lengths.

34 MPD/NICA like modules - transverse size $15 \times 15 \text{ cm}^2$, 4 nuclear interaction lengths.

Light collection:


– 6 WLS fibers from 6 sequentially scint. tiles
combined into one optical connector at the end of module.

Light readout:

10 MPPC ($3 \times 3 \text{ mm}^2$)/PSD module
(7 MPPC/MPD module)

Signal readout – 8 sampling ADC64

FHCaI is completely assembled and installed at the BM@N




Forward Quartz Hodoscope (FQH)

FQH covers the beam hole $15 \times 15 \text{ cm}^2$ in the FHCaI

- 16 quartz strips with sizes $10 \times 160 \times 4 \text{ mm}^3$;
- Light readout of each strip with 2 SiPMs from each strip ends;
- 64 readout channels – 4 TQDC.

FQH is ready for installation on the FHCaI


Status of the ScWall development and construction




Large cells (150x150x10mm³) - 134 pcs

Small cells (75x75x10mm³) - 36 pcs


Light collection – with WLS fiber glued in the groove.



large cells



small cell



Light readout: MPPC Hamamatsu S14160-1310(1.3x1.3 mm²)

Signal readout – 3 ADC64

Study of cells light output on LPI RAS synchrotron (March 2021)


Large cells

- Mean light output: 35 ph. el./MIP
- inhomogeneity of the light output: $\sigma \sim 7\%$




Small cells

- Mean light output: 55 ph. el./MIP
- inhomogeneity of the light output: $\sigma \sim 2\%$

Beam pipe downstream the SP-41 magnet



DCH



Development and production of the aluminum beam pipe downstream the SP-41 magnet will be performed by A. Kubankin group (Belgorod University).


S. Piyadin

Technical task is currently under discussion.


3D model development of the detectors after the SP-41 magnet is finished.

Beam pipe downstream the SP-41 magnet

S. Piyadin



Development of a BM@N reference metrological grid



Reference benchmarks: 48
Mean square error: 0.03 mm



- The BM@N coordinate system is fixed
- Measurements of the coordinates of reference marks and basic elements are performed
- BM@N reference metrological grid is developed
- Measurements of the relative position of BM@N elements are done



3D model of the BN@N experimental hall

S. Piyadin, S. Novozhilov, I. Kruglova

50 horizontal concrete blocks
600mm×1200mm ×10.5m are to be
Installed for biological protection



Main stages of geodetic measurements:

1. Measurements of GEM planes coordinates - done
2. Measurements of ion beam pipe segments
3. Reference measurements of GEM mechanics and ion beam pipe installed in SP-41 magnet
4. Measurements of the detector positions at SRC configuration
5. Measurements of the beam pipe downstream the SP-41 magnet

Summary:

Detector Subsystem

Upgrade Status

Beam pipe before the target

installed

Beam pipe downstream the target, in SP-41 magnet

June 2021

Beam pipe downstream the SP-41 magnet

December 2021

Trigger and T0 detectors

2021

Si beam tracking detectors, profilometers

2021

Forward Si detectors

3 full-size planes (2021)

STS BM@N

42 modules (2023)

292 modules (2024)

GEM

7 top half-planes +

7 bottom half-planes(assembled)

CSC

4 chambers 1065x1065 mm²(assembled)

2 chambers 2190x1453 mm²(03.2022, 06.2022)

ECAL

two arms (2022)

ToF-400 and ToF-700

full configuration

ZDC(MPD/CBM type)

installed


Backup

Simulation of 1st stage of hybrid central tracker: 3

Forward Si + GEM

A.Zinchenko, V.Vasendina




3 Forward Si + 7 GEM



DCM-QGSM model
Kr + Pb , $T_0 = 2.4$ AGeV

Aim:

- Optimization of detector positions and rotation angle of Forward Si stations
- Estimation of track reconstruction efficiency and momentum resolution






Simulation of hybrid central tracker for heavy ion

runs: STS +GEM

A.Zinchenko, V.Vasendina

QGSM model, Au+Au, $T_0 = 4$ AGeV




GEM



Hybrid STS + GEM tracker:

- ▶ 4 times increase in number of reconstructed tracks and Λ hyperons

BM@N GEM detectors



Schematic cross section of the BM@N triple GEM detector