


MPD/NICA TPC assembling (12.10.2021)

- TPC parameters
- ROC chambers
- TPC assembly
- front end electronics
- gas, cooling, laser and SC systems
- cabling and piping
- integration TPC to MPD
- time schedule




Presented by Sergey Movchan

JINR team: 24 persons
Belarus: 6 persons
UW Poland: 4-6 persons




- slides with actual info

MPD TPC parameters



Корпус TPC/MPD



TPC TDR – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>

S.Movchan TPC assembling, 8-th MPD collab meeting, Dubna, Oct 12 2021

12-Oct-21


Item	Dimension
Length of the TPC	340cm
Outer radius of vessel	140cm
Inner radius of vessel	27 cm
Outer radius of the drift volume	133cm
Inner radius of the drift volume	34cm
Length of the drift volume	170cm (of each half)
HV electrode	Membrane at the center of the TPC
Electric field strength	~140V/cm;
Magnetic field strength	0.5 Tesla
Drift gas	90% Ar+10% Methane, Atmospheric pres. + 2 mbar
Gas amplification factor	~ 10 ⁴
Drift velocity	5.45 cm/μs;
Drift time	< 30μs;
Temperature stability	< 0.5°C
Number of readout chambers	24 (12 per each end-plate)
Segmentation in φ	30°
Pad size	5x12mm ² and 5x18mm ²
Number of pads	95232
Pad raw numbers	53
Pad numbers after zero suppression	< 10%
Maximal event rate	< 7 kHz (Lum. 10 ²⁷)
Electronics shaping time	~180 ns (FWHM)
Signal-to-noise ratio	30:1
Signal dynamical range	10 bits
Sampling rate	10 MHz
Sampling depth	310 time buckets

ROC chambers status


24 pc tested ROCs in stock




ROC cleaning procedure



Wire pitch check set up




Test set up




+ 2 pc spare – tests in progress



ROC gate system (Minsk)



May 2021 test results:
huge noise in the ROC
FE electronics (up to
x 10 times) due to
GATE power supplies
(pulse type)




NEW prototypes:
- switch module
- power supplies:
+/- 300V & - 40V

NEW switch module





Test with ROC chamber
– **on this week**

TPC assembly (Bld.217) – common view



HV membrane – tested (**NO corona**)
Field cage roads – in assembly



ISO-6

$S=84 \text{ m}^2$

TPC assembly – **in progress**



TPC field cage rods assembly (Bld.40)


Set up for roads assembly




vivo X50 Pro
11 OKT. 2021 r., 14:51

Roads $D=30$ mm - 30pc assembled
Roads $D=60$ mm - assembling


TPC electronics: **block diagram** of one chamber readout



RCU and data concentrator based on commercial kits




SAMPA chip







TPC electronics: status

New version of the FE card:



2048ch readout system
powered via LVDB

Connection holes
for analog power
supply added



DAQ prototype:
32 FECs, RCU prototypes,
ROC, LVDB, interface board
to the Local Data Server -
tests ongoing



TPC electronics: status


- 477pc pre-serial FECs were produced (~32% of the whole amount).
- A new data transmission protocol with redundancy check between FECs and RCU (FEC Transfer Protocol - FTP) was developed and realized in the firmware. Testing is going.
- Testing of the readout system which includes 32 FECs, RCU prototypes, ROC, LVDB, interface board to the Local Data Server is ongoing towards having a 1/24 full-featuring readout system.
- The data transmission speed of 5 GB/s was achieved via PCIe between DCU card and Local Data Server.
- RCU v1 for 64 FECs is under adjustment:






Data concentrator ASIC (NRNU MEPhi)


Test set up diagram




PCB with CPGA-120 socket



PCB with caseless chip



Hub v1 testing plans



for more info - see E.Atkin's talk

TPC LV+HV system

LV&HV system based on CAEN rad. hard design:

(up to 2000 Gauss and 15 kRad)

- power converters A3486 AC/DC (380 V -> 48 V) – 15 pc
- EASY3000 crates – 13 pc
- LV module - A3100B (2÷7V/100A) – 55 pc

Status:

- TPC LV+HV system – *GSI tender finished (=> CAEN)*
- test system – tests ongoing

LV cables (halogen free, low smoke):

S=50 mm² – delivered to JINR (Dec 2019)


S=120 mm² – delivered to JINR (Dec 2019)

HV cables - ordered

LVDB boards (60 pc) - delivered

INP BSU (Minsk)

Team for cabling and piping – contracted



TPC gas system


Gas supply



Commissioning -
in progress




Racks

TPC volume
imitator



Status - **commissioned** (Bld.217)

TPC cooling system




Full set – delivered



TPC: FE serial cooling radiators (INP BSU Minsk)

Bottom cooling plates



Set of top cooling plates



Cu tube Din - 3.16 mm
Plates thickness - (4+4) mm



TPC cooling system: T-sensors calibrator

Calibrator

ЭЛЕМЕР-ТК-М150-К



Диапазон воспроизведения температуры, °C	-42...+95
Пределы допустимой абсолютной погрешности воспроизведения температуры в режиме жидкостного калибратора, °C	$\pm(0,02 + 0,0002 \times t)$
Нестабильность поддержания температуры за 30 мин, °C, не более	$\pm 0,01$
Нестабильность поддержания температуры в сменном блоке за 30 мин, °C	$\pm 0,005$
Неравномерность температуры в рабочем объёме, °C	от $\pm 0,01$
Диаметр ванны, мм	54




TPC cooling system: Pt100 calibration

Readout:
NI PXIe-4353, 24 bit ADC

Pt100 (grade AA): N=10pc
T=18 °C, 22 °C, 26 °C and 30 °C
T measurement – up to 19.4 h
R/O rate – 1.1 Hz




T=22 °C, row data






TPC cooling system: Pt100 calibration


T=18 °C



T=26 °C



T=30 °C



Pt100 calibration results:

Etalon sensor: $T = 21.9452^{\circ}\text{C} \pm 8.0\text{e-}4$ ($\sigma = 0.005^{\circ}\text{C}$)

After sensors calibration:

“T=18 °C” $\sigma = 0.009^{\circ}\text{C}$


“T=26 °C” $\sigma = 0.005^{\circ}\text{C}$ and

“T=30 °C” $\sigma = 0.009^{\circ}\text{C}$



Pt100 sensors precision (after calibration) can be achieved about 0.01°C for temperature range $T = +(18-30)^{\circ}\text{C}$

TPC laser calibration system: laser beams layout



½ TPC



TPC




micro-mirror bundles




laser beams layout –
fixed

- Laser “planes” - 4
- Micro-mirrors bundles per plane - 4
- Beams from micro-mirrors bundle - 7
- Laser “tracks”, **N** - **112x2=224**



TPC laser calibration system



Semi transparent mirror & prism






delivered





- full set of micro-mirror bundles - assembled
- 2 lasers – commissioned
- laser beam splitter – installed to flange
- laser beam monitors - prototype under tests

TPC cables and pipes integration

Trays layout concept




TPC services



FE cooling




Flange cooling



Optimization - in progress





TPC cables and pipes integration






Add structures for
cables and pipes
fixation

design –
in progress ...



Integration TPC to MPD: **concept**




24 tons,
max=0.41 mm





Rollers for
TPC moving



TPC schedule





MPD TPC status 2021: summary



Status:

• TPC:

C1-C2 and C3-C4 cylinders - assembled
TPC field cage assembly - Dec 2021

• ROC chambers (24pc) - 24 pc tested, +2 pc (spare)– under tests

• Electronics:

FE electronics (477 cards (32%)) - manufactured and delivered, testing
RCU controller - design done, prototype manufactured, preparation for tests
FE (32 cards) + ROC tests - preparation for tests
FE radiators mass-production - done
FE cards mass-production and tests - 2021 -> 2022

• Sub-systems:

local TPC DAQ prototype - tests in progress
Gas system - commissioned, integration to MPD started
Cooling system: full set of thermal panels - delivered, FE cooling radiators – delivered
HV+LV systems - 10% delivered, GSI tender finished -> CAEN
Laser calibration system: UV lasers and beam distribution systems - delivered, rest parts - ordered
Slow control system – integration to common TPC SC system **not started yet** (Win CC OA)

• Cabling and piping:

TPC cabling and piping - in progress
MPD TPC trays - in progress


• Integration TPC to MPD

TPC racks (8pc) layout - in progress
tooling for installation TPC to MPD - in progress

• TPC schedule

TPC installation to MPD - Nov 2022
MPD commissioning - Dec 2022

MPD event display - <http://db-nica2.jinr.ru/> (V.Krilov)



**Example
for TPC**

<http://nica.jinr.ru/>
<http://mpd.jinr.ru/>

TPC TDR – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>

Thank you for attention!

