


MPD TPC status (25.04.2022)

- TPC parameters
- ROC chambers
- Gating grid system
- TPC vessel assembly
- Front end electronics
- Gas, cooling, laser and SC systems
- Cabling and piping
- Integration TPC to MPD
- Time schedule



Presented by Sergey Movchan

JINR team: 24 persons

Belarus: 6 persons


UW Poland: 5 persons

ROC chambers status


24 pc tested ROCs in stock




ROC cleaning procedure



Wire pitch check set up



Test set up



+ 2 pc spare – tests in progress



Set up for pads calibration respect to ROC alignment pins




Leica MS60 - 1 second

Leica AT960 ± 10 mkm $+5$ mkm/m


Leica AT403 ± 15 mkm $+6$ mkm/m

Scanner AS1+AT960 ± 50 mkm

Calibration scheme



Pad plane unflatness: example



+/- 30 mkm

ROC frame geometry check

расстояние 1


Контр фигура: точка 1, Фигура: точка 2

	Номинальный	Измер	Отклонение	Тест
Расстояние Y	500.000	500.098	0.098	○

расстояние 2



Контр фигура: точка 1, Фигура: точка 3

	Номинальный	Измер	Отклонение	Тест
Расст (3D)	858.220	858.366	0.146	○




OK!

Pads position measurement scheme



Pads geometry deviation from nominal: example



**Deviation from nominal –
up to 150 mkm (X and Y)**

ROC alignment pins (deviation from nominal): example

up to 80 mkm

Full set of photogrammetry marks for all ROC chambers




Summary:

- measurements for all 30 pc ROC – **done**
- ROC pins-pads alignment – **in progress**

ROC gating grid system (Minsk)



Pulse rise time - 500 ns, OK!



Mass-production – started

Delivery to JINR – Dec 2022


FE radiators and LVN9+ FE power cables



Delivered – Dec 2021

LVN9+ FE power cables

LVN9+FE power cables: one board




60 pc were send back to Minsk.
Power cables modification – **done**

Test of LVN9 with cooling
radiators under full load (analog –
70 A, digital – 50 A) – **in progress**

Set up for cooling tests (ROC+FE)


Set up



Chiller




LV power






Tests – in progress

TPC vessel assembly (Bld.217) – common view



HV membrane – tested (**NO**
corona)
Field cage roads – in assembly




TPC assembly – **in progress**



TPC field cage rods assembly

Set up for field cage elements assembly




Set up for rods assembly



Rods D=30 mm – 30 pc assembled


Rods D=60 mm – **assembling started**

TPC service wheel: status (Bld.217)




**One service wheel -
assembled**


TPC electronics: **block diagram** of one chamber readout



SAMPA chip




RCU and data concentrator based on commercial kits





TPC electronics: test set up

Production version of the FE card:



**2048ch readout system
powered via LVDB**

**Connection holes
for analog power
supply added**



DAQ prototype:
32 FECs, RCU prototypes,
ROC, LVDB, interface board
to the Local Data Server -
tests ongoing




TPC electronics: status



- 467 FECs of 1500 were produced.
- Tests of the FEC basic functionality were shown the target characteristics (Noise and stability).
- Testing of the readout system for one ROC is ongoing.



FECs Production status:



**8 ROCs chambers will be completed
at the end of 2022.**

ASIC Hub v1: structure and specs

main functions: data concentration from two SAMPA chips and their transfer to counting room via fast 2.56 Gb/s bi-directional interface



- 1) Process – TSMC65 LP MS RF
1P9M_6X1Z1U_RDL;
- 2) Chip area – 1980 x 1980 um;
- 3) Bond pads – 111 (37 type CUP staggered & 74 type IN-LINE)
Pad size – 57 x 69 um
Pad Pitch – 60 um
- 4) Technological run of Nov. 2020
- 5) Readiness – July 2021
- 2 types of packaging: CPGA 120 & caseless

25-Apr-22




Power consumption

S.Movchan TPC status, a MPD collab. meeting,
April 25, 2022

< 500 mW

Hub v1 photos (chip & case)


Fabricated are 10 pcs in CPGA-120 package and 80 pcs - caseless



April 25, 2022

The lab testbench in calibrated beam

Purpose - checking functionality of the chip blocks against heavy particles.
Tests were done at PNPI, Gatchina in Feb. 2022



Chip status – see talk E.Atkin
27/04/2024

TPC LV+HV system

LV&HV system based on CAEN rad. hard design:

(up to 2000 Gauss and 15 kRad)

- power converters A3486 AC/DC (380 V -> 48 V) – 15 pc
- EASY3000 crates – 13 pc
- LV module - A3100B (2÷7V/100A) – 55 pc

Status:

- TPC LV+HV system – GSI tender finished (=> CAEN)



Expected delivery date:

to GSI – Sept 2022

to JINR – end of 2022 – beginning of 2023

CANCEL

New ordering –
in progress

- test system – tests ongoing

LV cables (halogen free, low smoke):

S=50 mm² – delivered to JINR (Dec 2019)

S=120 mm² – delivered to JINR (Dec 2019)


LV bars – delivered to JINR (Dec 2021)

HV cables - ordered

LVDB boards (60 pc) - delivered

INP BSU (Minsk)

Team for cabling and piping – contracted (Minsk)




TPC gas system

Gas supply






Racks

TPC volume imitator




Tests - in progress

TPC cooling system



**Full set –
delivered**



TPC: FE cooling radiators (INP BSU Minsk)

Bottom cooling plates



Set of top cooling plates




Cu tube Din - 3.16 mm
Plates thickness - (4+4) mm


TPC+ECAL cooling system:
start tender – may 2022

TPC laser calibration system: laser beams layout



½ TPC



TPC




micro-mirror
bundles




Laser “planes” - 4
 Micro-mirrors bundles per plane - 4
 Beams from micro-mirrors bundle - 7
 Laser “tracks”, N - $112 \times 2 = 224$

Laser beams layout – fixed
 Integration to MPD – not
 started yet



TPC laser calibration system



Semi transparent mirror & prism




delivered



- full set of micro-mirror bundles - assembled
- 2 lasers – commissioned
- laser beam splitter – installed to flange
- laser beam monitors - prototype under tests



TPC cables and pipes integration






Structures for
cables and pipes
fixation





design –
in progress ...





TPC cables and pipes integration



design –
in progress ...





Rollers for TPC moving



25-Apr-22

TPC schedule




FE mass-production (537 pc) – Sept 2022
FE mass-production (933 pc) – ... 2023 ... ???
ROC to TPC
 - Jan and May 2023
TPC cosmic test (bld.217) - summer 2023
Cabling & piping on MPD - Jun-Sept 2023
TPC to MPD hall
 - Aug 2023
TPC install and align
 - Sept 2023
MPD dry run
 - 2023-2024

Shift = 12 month

MPD on the Collider beams

MPD event display - <http://db-nica2.jinr.ru/> (V.Krilov)





**Example
for TPC**

<http://nica.jinr.ru/>
<http://mpd.jinr.ru/>

TPC TDR – <http://mpd.jinr.ru/wp-content/uploads/2019/01/TpcTdr-v07.pdf>

Thank you for attention!



MPD TPC status 2022: **summary**



Status:

• **TPC:**

C1-C2 and C3-C4 cylinders
TPC field cage assembly
TPC vessel ready
TPC service wheels assembly

- assembled
- **May -> June 2022**
- **Sept 2022**
- one – assembled, second - ongoing ...

• **ROC chambers**



Test of FE (32 cards) with ROC
Flat cables (28 sets + spare)
FE radiators (28 sets)
LVN9 stabilization boards (28 sets)
FE power cables (28 sets)
Alignment pins (**120 pc**)
Pads alignment (calibration)
Assembly FE with ROC
Test of installation ROC to TPC
Gating Grid system (GGS)

- 24 pc tested + 2 pc (spare)+4 pc
- **preparation ongoing**
- ready
- **narrow plates– modification in progress**
- **tests in progress**
- ready
- manufactured, ready
- April 2022 (laser scanner and photogrammetry) – **in progress**
- **awaiting**
- move to May 2022 (will be used mock up at bld.205)
- Dec 2022

• **Electronics:**

FE electronics (**537 cards (36%)**)
FE electronics (**933 cards (62%)**)
RCU controller
Integration RCU controllers to TPC
RCU mass-production

- **July 2022**
- **... 2023 ... ???**
- design done, prototype manufactured, preparation for tests
- **2022**
- **2023**



MPD TPC status 2022: **summary**



Status:

Sub-systems:

DAQ:

- local TPC DAQ prototype - tests in progress
- DAQ set up #1 (ROC test at bld.40) - ok
- DAQ set up #2 (FE tests at room 107) - ok
- DAQ set up #3 (FE tests at Minsk) - April 2022 - > May 2022

Gas system - tests ongoing, integration to MPD started

TPC cooling system - tender (Feb-March 2022 - > May 2022) **on critical path**



HV+LV systems (CAEN) - 10% delivered, GSI tender finished, delivery to JINR – **CANCEL**
new tender at JINR – > May 2022

Laser calibration system - UV lasers and beam distribution systems - delivered, rest parts – ordered

Slow control system – integration to common TPC SC system **not started yet** (Win CC OA)

• Cabling and piping:

- TPC cabling and piping design - in progress
- TPC trays design - in progress
- TPC trays manufacture - spring 2023
- LV bars and LV cables manufacture - spring 2023
- HV cables manufacture - spring 2023
- Gas piping - spring 2023
- Cooling piping - spring 2023
- Patch panels - spring 2023



MPD TPC status 2022: summary



Status:

- **Integration TPC to MPD:**

TPC racks (8pc)

- layout optimization in progress

TPC rails (calculations, manufacture) - Feb 2022 → May 2022

on critical path

Rails installation to MPD, tests

- summer 2022

Tooling for installation TPC to MPD:

concept

- fixed

design

- started ... May 2022 – August 2022 (4 month)

tooling manufacture

- June - > Sept 2022 – Feb 2023 (6 month)

delivery to JINR

- March 2023

TPC cooling systems (2 pc)

- Sept 2023

- **TPC schedule:**

TPC installation to MPD

- start Sept 2023

MPD dry run

- 2023-2024 (shift by 12 month)