

## Status of the MPD integration


Viacheslav Golovatyuk (JINR)


### The MPD complex














# List of the activities towards realization of our plan – Preparation the MPD for running on the collider beams

1	Subsystems of MPD: TOF, FHCal and FFD, DAQ, Trigger	On the stage of production and tests according to schedule
	TPC 50-80 % of the FEE ECAI. 16 sectors out of 25	Have a chance to start in 2023 in not complete configuration
2	Electronics Platform	Tech. documentation is ready, signing contract on production Could be in simplified configuration
3	Cryogenics Infrastructure of the Solenoid. Gas&Liquid N <sub>2</sub> and He pipes, LHe, LN <sub>2</sub> tanks	LHe and LN2 pipes are ordered and partly produced Problem with delivering to JINR
4	Cooling systems for the FE electronics TPC and Ecal and thermostability of TPC	Tender on design and production  Have a chance to start with a partly constructed cooling system
5	Equipment for detectors integration The lifting platform Equipment for Ecal installation Equipment for TOF installation Equipment TPC installation Platforms for FHCal fixation in the poles Equipment for beampipe installation	In production Technical documentation in preparation In production In production In production Technical documentation in preparation

#### **Prospect of contracts performance concluded by JINR with companies** Сумма **Number of**

Subject

договора,

Comments

Country

Company

Country	Company	Contract	Subject	договора, EUR	Comments
Germany	Institut fuer Luft und Kaeltertechnik Gemeinnuetzige Gesellschaft mbH	08626319/21108253 6-74 от 11/01/2022	Contract with ILK for the assembly and commissioning of refrigerator	Agreement is signed	<ul><li>1.Self-assembly,</li><li>2. Resumption of cooperation if possible.</li><li>Remote consultation as agreed (to be discussed with ILK)</li></ul>
Germany	STOHR ARMATUREN GmbH & Co KG, Germany	08626319/21644-73 б/д	Flexible pipeline No. 1; Flexible pipeline No. 2; Flexible pipeline No. 3	100% payment	Search for delivery options from Germany.
Italy	Costruz. Apparec. Elettron. Nucleari CAEN, Italy	08626319/210825- 74 от 07/10/2021	Test equipment for TPC (LV)	50% payment	OK! Shipment from CAEN scheduled for April 20, 2022
Poland	FRAKO TERM, Poland	08626319/211092- 73 от 08/02/2021	Thermal Screen for liquid nitrogen	100% payment	The firm plans to ship the screens by the end of April 2022.
England	A.S.Scientific Products Ltd, UK	08626319/211259- 73 от 19/04/2021	Cryogenic pipeline 60m, supports made of low-carbon galvanized steel	Agreement signed	The supplier is ready to fulfill its obligations, subject to delivery from the UK on its own. Search for another producer.
England	A.S.Scientific Products Ltd, UK	08626319/21104052 4-74 от 29/11/2021	Heater housing with vacuum insulated helium heater with spare parts	Agreement signed	Search for delivery options from UK.
Czech Republic	CHART FEROX A.S.	08626319/211053- 73/CHART	Cryogenic stationary Liquid Nitrogen Tanks	30% payment	Search for delivery options

VT 21/18

Q145680 от

14/04/2021


## Temporary scheme of cooling at 4,5 K

In case we have no ordered pipes:

- Regular LHe pipe with LN2 shield.
- Regular LN2 pipes

#### Minimal configuration :

- LHe Tank (ready)
- LN2 transport tank (ready)
- Two heaters (ordered)
- Pipes between refrigerator and control Dewar (ready)
- LN2 manifold (TS is finalized)
- Other pipes (in process of ordering)
- Refrigerator (assembly will start at the end of May)
- Control Dewar (needed to be assembled, consultation with ASG)



### Mass production of half sectors for ECal

700 modules out of 800 modules produced in Russia 800 modules should be delivered before July from China

It is important for us to produce and install all sectors at the beginning.

Otherwise we need a big efforts reassemble all cables to install the rest of the sectors

We have a chance to complete production of 100% of Ecal barrel modules till the end of 2023, it means production of additional 800 modules. This goal is feasible in case of availability of all required materials.

For that we need additional founds. China team is ready to provide FE for this part of of sectors.

JINR site is able to build this amount of modules till end of 2023. Money redistribution is required.



For completing the calorimeter up to 100% (additional 800 modules) Materials -

Lead plates - 1 M\$

Light guides -0.6 M\$

Assembly of modules -1.5 M\$

Total: about 3 M\$.

Assembly of semi-sectors can be done on time

The production of 800 modules is difficult task to achieve in a short time.

### **Activities to prepare Solenoid for the cooling**

#### 1. Work with Solenoid

- installation into Magnet Yoke
- alignment of Cold mass
- pressure test of Thermal shield and Cryostat cold mass
- replacement of flanges (transport to the working)
- vacuum test of Solenoid vessel, leak test of Cryostat
- connection temperature probes cables
- assembling Magnet Yoke
- alignment
- installation of Top platform
- chimney installation

## 2. Satellite Refrigerator Unit (SRU) - A new contract with ILK

- Development of the new control system for the SRU
- Spare parts for the SRU
- Assembly of the SRU
- Cold test of the SRU at 4.5K

### 3. Cryogenics infrastructure

- construction of platform for LN<sub>2</sub> tanks and other equipment
- pipes for LN<sub>2</sub> from tanks to the MPD hall
- liquid and gas pipes for N<sub>2</sub> and He inside of MPD Hall
- pipes on the cryogenic platform
- LHe tank in the MPD Hall
- external lines for gas direct and return He and  $N_2$
- Two LN tanks installation

### 4. Power Supplies and Control system preparation

- electricity in the MPD hall
- water for cooling system
- control system

# Milestones of MPD assembling in 2020-2023

		Year 2020
1	July 15.	- MPD Hall and pit are ready to store and unpack Yoke parts
2	August	- The first 13 plates of Magnet Yoke are assembled for alignment checks
3.	Sept 15-Oct 1.	- Solenoid is ready for transportation from ASG (Italy)
	*	- Solenoid arrived
5.	Nov-Dec	- Assembling of Magnet Yoke
		Year 2021
6.	July-Aug	- Solenoid installation into Iron Yoke and alignment
7.	Aug - Dec	- Electrical, pressure and vacuum tests
		Year 2022
8.	April 30	- Cables for Solenoid probes signals are installed.
•		Ready for assembling of Iron Yoke
	Apr 30 - June 15	- Assembling Iron yoke, Cryogenic platform and Cryostat. Vacuum test
10.	June 16t - July 30	- Solenoid cooling down to Liquid Nitrogen temperature
11.	September 30th	- Cryogenic infrastructure ready
12.	Oct 1st - Nov 20	- Cooling down to LHe temperature
13.	Nov 20th – Dec 30.	- Magnetic Field measurement
		Year 2023
14.	Jan 20 -Feb 15	- Support Frame installation
15	Feb 15 <sup>th</sup> – April 10th	- Installation of ECal half sectors

- Switch on the MPD, Commissioning

	rear 2025
14. Jan 20 -Feb 15	- Support Frame installation
15. Feb 15 <sup>th</sup> – April 10th	- Installation of ECal half sectors
16. March-July	- Electronics Platform assembling,
17. April-July	- Cabling
18. April 1 – June 5 <sup>th</sup>	- Installation TOF modules
19. May15 <sup>st</sup> – August 1 <sup>st</sup>	- TPC installation
20. June-July -	- FHCal, Cosmic Ray test system

21. August