



Construction Management Information System at JINR

Alejandro Rodríguez Alvarez (JINR-CEADEN).

2022.10.26



To be sent to publication:

"Physics of Particles and Nuclei"

CONSTRUCTION MANAGEMENT INFORMATION SYSTEM AT JINR

C. Ceballos,^{1,*} A. A. Kolozhvari,¹ A. G. Dolbilov,¹ R. N. Semenov,¹ E. A. Tsapulina,¹
A. Rodriguez,^{1,2} A. D. Sheremetiev,¹ and Yu. A. Murin for the MPD-ITS Collaboration¹

¹*Joint Institute for Nuclear Research, Dubna, Russia*

²*Center for Technological Applications and Nuclear Development, Havana, Cuba.*

The commissioning of an all-around Construction Management information System (CMIS) was recently completed as a joint effort of two JINR Laboratories (LHEP and LIT). The system is particularly useful for the fine-grained control and continuous feedback of the production of complex multipart objects like the detectors subsystems composing the MPD and BM@N experiments of the NICA facility at LHEP. Currently, the CMIS is meant to be used to follow the production of silicon tracker detectors at the STS department of the LHEP at JINR, although it would as well be used by any other hardware production projects related to JINR whose complexity would make it very hard to fulfilling its quality and timing requirements otherwise.

1. INTRODUCTION

Two of the major experiments of the NICA collider project at JINR are the MultiPurpose Detector (MPD) [1] and the Baryonic Matter at Nucleotron (BM@N) [2]. In both cases the production of the silicon tracker of this facilities will be led by the STS department of the LHEP at JINR under the project names of MPD-ITS and BM@N-STs, respectively. These are complex setups that require the implementation of a precise workflow of components production, multi-stage assembly and test to be coordinated between several institutions [3, 4]. For this reason it was decided to implement for both projects a construction management information system (CMIS) that would allow for a tight control of the production process for the timely achievement of both projects goals. The system contains a Web application installed on an application server that is accessed by the clients through the internet and

* Electronic address: ceballos@jinr.ru



Construction Management Information System

| | |
|-----------------------|---|
| Customer | Joint Institute for Nuclear Research 6 Joliot-Curie St Dubna Moscow Region Russia |
| Contact person | Yuri Murin |
| Date | 11. 11. 2019 |
| Authors | Ján Jadlovský Henrieta Telepovska Jakub Čerkala Vasil' Vančík |

All-around multiple-projects handler.

It is composed of the following base modules:

- » **Resources Module**
 - » Members
 - » Institutes
- » **Project Module**
 - » Project Definition and Planning
 - » Project Management and Resources
 - » Construction Data
 - » Activities
 - » Finances
 - » Reports
- » **Administration**
- » **Help**

Information System for ALICE Upgrade Construction Management System



ALICE UPGRADE CONSTRUCTION MANAGEMENT SYSTEM

January 2019

Ver. 3

CERN

KYBERNETIKA, s.r.o., Košice

Orgovánová 4

040 11 Košice

Slovak republic



KYBERNETIKA s.r.o.
Automatizované systémy riadenia

Construction Management Information System

Customer

Joint Institute for Nuclear Research
6 Joliot-Curie St
Dubna
Moscow Region
Russia

Contact person

Yuri Murin

Date

11. 11. 2019

Authors

Ján Jadlovský
Henrieta Telepovska
Jakub Čerkala
Vasil' Vančík




Construction Management Information System


Customer Joint Institute for Nuclear Research
6 Joliot-Curie St
Dubna
Moscow Region
Russia


Contact person Yuri Murin

Date 11. 11. 2019

Authors Ján Jadlovský
Henrieta Telepovska
Jakub Čerkala
Vasil' Vančík







Activities are actions performed on Components that may change their Physical/Functional^(*) status.

Activity: MAPS Chip Classification of ChipXX





Component: MAPS ChipXX



Result: MAPS ChipXX [Physical Satus] = <physical_status_value>
MAPS ChipXX [Functional Satus] = <functional_status_value>

(*) All possible Physical and Functional statuses of a component are declared on the 'Component Type' definition.
The possible result of an Activity are combinations of Physical and functional statuses and are declared on the 'Activity Type' definition.



LIT

CMIS

File

(Oracle)

attachments

EOS




(SSH)

webAp


p(HTTPS)

API

(HTTP GET/POST & functions SOAP)



| Activity Name | Activity Type | Start Date | End Date | Location | Activity Status | Activity Result |
|--|--|------------|------------|----------|-----------------|-----------------------------|
| [82] Another test | [81] DRW: Send DRW Unit for production | 23.12.2020 | | | [81] OPEN | |
| [81] DRW: Jig drawing JIGDRW T080.000.185 Beam | [81] DRW: Send DRW Unit for production | 23.12.2020 | 23.12.2020 | | [82] CLOSED | [43] OK_SENT_FOR_PRODUCTION |
| [41] 123 | [41] Test | 17.12.2020 | | | [81] OPEN | |



The following operations are supported. For a formal definition, please review the [Service Description](#).


- ActivityAttachmentCreate
- ActivityAttachmentRemove
- ActivityChange
- ActivityComponentAssign
- ActivityComponentRemove
- ActivityCreate
- ActivityMemberAssign
- ActivityMemberChange
- ActivityMemberRemove
- ActivityParameterChange
- ActivityParameterCreate
- ActivityParameterRemove
- ActivityRead
- ActivityReadOne
- ActivityTypeRead
- ActivityTypeReadAll
- ActivityUriChange
- ActivityUriCreate

(SSO cookie)

(Kerberos credentials automatically renewed)



Custom Assembly & Testing programs

Direct HW interface to DB




JINR SSO:

- » Registered service accounts.
- » Kerberos credentials.
- » Access cookies acquired through 'get-sso-cookie.py'.




JINR SSO:


- » Web access.
- » Registered JINR-SSO users.
- » Role-based access rights.




MPD-ITS COLLABORATION PROJECT




CBM-BM@N STS COLLABORATION PROJECT




Only the Outer Barrel:




☑ 42x – Staves



☑ 588x – HIC




☑ 8232x – MAPS







☑ 4x - Stations





☑ 44x - Ladders



☑ 292x - Silicon strip modules.



Custom-made GUI



CMIS web interface

Activities: MPD-ITS

Total Records: 60

| | Activity Name | Activity Type | Start Date | End Date | Location | Activity Status | Activity Result | |
|-------|-----------------------------------|--|------------|------------|-------------------|-----------------|-----------------|---|
| [430] | OBFPCL ElectricTest AL003479 | [458] Outer Barrel FPC Electrical Test | 09.09.2021 | 09.09.2021 | [293] JINR, Dubna | [242] CLOSED | [586] OK | 2 |
| [429] | BLOBFPCL CrossCableSolder A003479 | [457] Outer Barrel FPC Cross Cable Soldering | 09.09.2021 | 09.09.2021 | [291] JINR, Dubna | [242] CLOSED | [583] OK | |
| [428] | CROSSCBL AttachLotInfo CX011 | [377] Cross Cable Lot Attach Information | 09.09.2021 | 09.09.2021 | [290] JINR, Dubna | [241] OPEN | | |
| [427] | BLOBFPC ElectricalTest A003479 | [368] Blank Outer Barrel FPC Electrical Test | 09.09.2021 | 09.09.2021 | [287] JINR, Dubna | [242] CLOSED | [572] OK | 2 |
| [426] | BLOBFPC ElectricalTest A003479 | [368] Blank Outer Barrel FPC Electrical Test | 09.09.2021 | 09.09.2021 | [287] JINR, Dubna | [242] CLOSED | [572] OK | |
| [425] | BLOBFPC ElectricalTest A003479 | [368] Blank Outer Barrel FPC Electrical Test | 09.09.2021 | 09.09.2021 | [287] JINR, Dubna | [242] CLOSED | [572] OK | 1 |
| [424] | BLOBFPC Metrology A003479 | [371] Blank Outer Barrel FPC Metrology | 09.09.2021 | 09.09.2021 | [285] JINR, Dubna | [242] CLOSED | [569] OK | |
| [423] | BLOBFPC Metrology A003479 | [371] Blank Outer Barrel FPC Metrology | 09.09.2021 | 09.09.2021 | [285] JINR, Dubna | [242] CLOSED | [569] OK | |
| [422] | BLOBFPC Visinspect A003479 | [373] Blank Outer Barrel FPC Visual Inspection | 09.09.2021 | 09.09.2021 | [286] JINR, Dubna | [242] CLOSED | [595] OK | |
| [421] | BLOBFPC Metrology A003479 | [371] Blank Outer Barrel FPC Metrology | 09.09.2021 | 09.09.2021 | [285] JINR, Dubna | [242] CLOSED | [569] OK | |
| [410] | CROSSCBL AttachLotInfo CX013 | [377] Cross Cable Lot Attach Information | 03.09.2021 | 03.09.2021 | [290] JINR, Dubna | [241] OPEN | | |
| [409] | CROSSCBL AttachLotInfo CX015 | [377] Cross Cable Lot Attach Information | 03.09.2021 | 03.09.2021 | [290] JINR, Dubna | [241] OPEN | | |
| [408] | OBFPCL ElectricTest AL002113 | [458] Outer Barrel FPC Electrical Test | 02.09.2021 | 02.09.2021 | [293] JINR, Dubna | [242] CLOSED | [586] OK | |
| [407] | CROSSCBL AttachLotInfo CX001 | [377] Cross Cable Lot Attach Information | 02.09.2021 | 02.09.2021 | [290] JINR, Dubna | [241] OPEN | | 1 |
| [406] | BLOBFPCL CrossCableSolder A003122 | [457] Outer Barrel FPC Cross Cable Soldering | 02.09.2021 | 02.09.2021 | [291] JINR, Dubna | [242] CLOSED | [583] OK | |
| [405] | BLOBFPCL CrossCableSolder A003546 | [457] Outer Barrel FPC Cross Cable Soldering | 31.08.2021 | 31.08.2021 | [291] JINR, Dubna | [242] CLOSED | [583] OK | |
| [404] | BLOBFPCL CrossCableSolder A003545 | [457] Outer Barrel FPC Cross Cable Soldering | 31.08.2021 | 31.08.2021 | [291] JINR, Dubna | [242] CLOSED | [584] NOK | |
| [403] | BLOBFPC ElectricalTest A003520 | [368] Blank Outer Barrel FPC Electrical Test | 31.08.2021 | 31.08.2021 | [287] JINR, Dubna | [242] CLOSED | [573] NOK | |
| [402] | BLOBFPC Metrology A003545 | [371] Blank Outer Barrel FPC Metrology | 31.08.2021 | 31.08.2021 | [285] JINR, Dubna | [242] CLOSED | [570] NOK | |
| [401] | OBFPCL ElectricTest AL002112 | [458] Outer Barrel FPC Electrical Test | 29.08.2021 | 29.08.2021 | [293] JINR, Dubna | [242] CLOSED | [586] OK | 5 |

(Total: 800 pcs)

FPC production

BOBFPC

CC


Testing


Soldering

OBFPCL

Testing

Storage







- ☑ 82x - Visual Inspection of STS MST Sensor
- ☑ 3880x - Visual Inspection of STS Microcable
- ☑ 207x - Visual Inspection of STS SMX
- ☑ 27x - Visual Inspection of STS FEB
- ☑ 76x - Visual Inspection of STS LDO
- ☑ 120x - Visual Inspection of STS Shield
- ☑ 198x - Electrical Test of SMX

- The deployment of the CMIS on the JINR's infrastructure represent a novelty for this institute since no such a system had been used before.
- The system is particularly useful for the fine-grained control and continuous feedback of the production of complex multipart objects like the detectors subsystems composing the different experiments of the NICA facility at LHEP.
- Offer the possibility of creating a fully customized interfaces using any desired programming language to better adapt to the structure and requirements of any project of this type, using the web API collection.
- At present it is used by two of the NICA projects (MPD-ITS and BM@N-STs) but since it is centrally hosted at JINR(LIT) it might be used by any other project that could benefit from it.

Thank you for your attention!