




SPD cryogenic system



Outline

1. Cryogenic system
2. Cryogenic equipment
 - 2.1. Helium system
 - 2.2. Nitrogen system
 - 2.3. Other systems
3. Steps creation & costs
4. Conclusions





2.1. Helium system

Refrigerator



| |
|-------------------------|
| 100 W @ 4.5 K (140 l/h) |
|-------------------------|


| |
|--------|
| 16 g/s |
|--------|

| |
|---------|
| 3.0 Mpa |
|---------|

| |
|-------------------|
| 2000 mm x 3500 mm |
|-------------------|


Pipeline s

| Rigid pipes | Flexible pipes |
|-----------------|-----------------|
| 220 m | 40 m |
| ø60 mm high pr. | ø60 mm high pr. |
| ø100 mm low pr. | ø100 mm low pr. |





2.2. Nitrogen



Cryogenic tanks

1 platform, 2 – Storage tanks for LN₂, 2 – Storage tank for LAr, 3 – Storage tank for LCO₂, 4 – Evaporator for LAr, 5 – Evaporator for LCO₂, 6 – Storage bottles, 7 – Equipment room

Pipeline

Cryogenic line

Warm line


LN₂ – 120 m (rigid tube)
LN₂ – 40 m (flexible tube)

Ar – 100 m (rigid tube)
N₂ – 100 m (rigid tube)
CO₂ – 100 m (rigid tube)



2.3. Other systems

- Vacuum system



Diffusion vapor pump and pumping station with two foreline pumps


- Pneumatic system





2.3. Other systems

- Cryogenic system control





3. Estimating the costs and power consumption of systems

| | Name of system | Costs, κ\$ | Power, kW |
|---|--------------------------|------------|-----------|
| 1 | Cryogenic plant | 3 330 | 2 |
| 2 | Helium pipeline | 500 | - |
| 3 | Nitrogen system | 1 500 | 2 |
| 4 | Vacuum subsystem | 500 | 14 |
| 5 | Pneumatic subsystem | 50 | 3 |
| 6 | Cryogenic system control | 500 | 2 |
| | Total | 6 380 | 23 |



Steps creation

| SPD | 2022 | | | | 2023 | | | | 2024 | | | | 2025 | | | | 2026 | | | | 2027 | | | |
|--------------------------|------|----|-----|----|------|----|-----|----|------|----|-----|----|------|----|-----|----|------|----|-----|----|------|----|-----|----|
| | I | II | III | IV | I | II | III | IV | I | II | III | IV | I | II | III | IV | I | II | III | IV | I | II | III | IV |
| Cryogenic plant | | | | | | | | | | | | | | | | | | | | | | | | |
| Helium pipeline | | | | | | | | | | | | | | | | | | | | | | | | |
| Nitrogen system | | | | | | | | | | | | | | | | | | | | | | | | |
| Vacuum system | | | | | | | | | | | | | | | | | | | | | | | | |
| Pneumatic system | | | | | | | | | | | | | | | | | | | | | | | | |
| Cryogenic system control | | | | | | | | | | | | | | | | | | | | | | | | |



Technical task



Contract execution



Assembly & Test



Commissioning



4. Conclusions

The cooling capacity, mass flow rate and working cycles of the cryogenic plant are calculated.

The development of technical tasks for a cryogenic plant and a platform for cryogenic storage tanks is in the active phase.

The work is carried out according to the plan.



Thank for your attention!