
MPD TPC status (08.11.2022)

- TPC vessel assembly
- ROC chambers
- Gating grid system
- Electronics
- Gas and cooling systems
- LV+HV system (CAEN)
- Cabling and piping
- Integration TPC to MPD
- Time schedule




Presented by Sergey Movchan

JINR team: 24 persons

Belarus: 10 persons


TPC vessel assembly (Bld.217) – common view











C1-C2 and C3-C4 cylinder – assembled
TPC service wheels (2pc) - assembled
HV membrane – tested


TPC field cage assembly - Jan-Feb 2023

TPC vessel ready

- March 2023

TPC assembly – in progress

TPC service wheels: status (Bld.217)






Thermal panels (12pc)

Both service wheels - assembled

TPC field cage rods assembly



Set up for rod D=30 mm assembly



Rods (30 pc) - assembled

TPC field cage rods assembly

Set up for tubes assembly









Set up for D=60 mm rod assembly



Rods D=60 mm – assembling started


N=144+11spare =155 pc - ready

ROC chambers status


24 pc tested ROCs in stock



ROC cleaning procedure



Wire pitch check set up









ROC: FE cards integration

Card grounding



Additional cooling plate



- FECs can be mount after ROC installation
- Now FECs can be place in one level

Set up for pads calibration respect to ROC alignment pins






Leica MS60 - 1 second

Leica AT960 +/-10 mkm +5 mkm/m

Leica AT403 +/-15 mkm +6 mkm/m


Scanner AS1+AT960 +/-50 mkm

Pad plane unflatness: example




+/- 30 mkm

Pads geometry deviation from it nominal position:



Deviation pads from it nominal position: systematic - up to 150 mkm (X and Y)

ROC alignment marks



Full set of photogrammetry marks for all ROC chambers



it nominal position - up to 80 mkm

Summary:

- measurements to do for all 30pc ROCs
- ROC marks and pads calibration (computation) respect to ROC

"reference hole" - in progress

ROC gating grid system (Minsk)



Pulse rise time - 500 ns, OK!



Prototype



power supply test


Mass-production – started

Delivery to JINR – Dec 2022



TPC electronics: test set up


Production version of the FE card:




- RCU prototypes
- 2. FECs on the ROC (62 pc)
- 3. LV power supply
- 4. DCU card connected with RCUs via fibers
- 5. Readout server

Analog power supply connector for SAMPA board

3968ch readout system powered via LVDB





DAQ prototype:


62 FE cards, RCU prototypes, ROC, 2pc LVDBs, server interface board - tests ongoing

TPC electronics: status



- **727** FECs of 1500 were produced.
- Tests of the FEC basic functionality were shown the target characteristics (Noise and stability).
- Testing of the readout system for one ROC is ongoing.


TPC FE cards production status



11 ROCs chambers will be completed at the end of 2022.

FE power cables


Option No2







Option No1



60 pc LVN9 were send back to Minsk:

- modification connection of power cables to LVN9 in progress
- modification of LVN9 output voltages to FECs - in progress
- test of LVN9 with cooling radiator under full load (analog 70 A, digital 50 A) in progress

TPC R/O electronics: power consumption

Electronics	Power
SAMPA FEE (2*62*24 = 2976 pc)	$(1,016-1,2)$ W x 2976 ~ $(3024 \div 3571)$ W
FPGA (62*24 = 1488 pc)	(2,55-2.65) W x 1488 ~ (3792 ÷ 3943) W
LVDB (48 pc)	$(76,1-80)$ W x 48 $\sim (3652 \div 3840)$ W
R/O controllers (24 pc)	200 W x 24 ~ 4800 W
TOTAL:	(15268 ÷ 16154) W
	P~16 kW

FE cooling radiators (INP BSU Minsk)

Bottom cooling plates





Set of top cooling plates



Cu tube Din - 3.16 mm Plates thickness - (4+4) MM



TPC+ECAL cooling system: tender -> INP BSU, Minsk JINR-INP contract – in progress

ROC+FE cooling set up

Set up



Tests – in progress


Chiller



LV power



Cooling: sensors





T sensor based on Pt100











ROC + **FE** cooling: results

ROC + pad sensors

PAD plane Pad plane Алюминиевый корпус

FE card sensors



Air: T=23 degree (C)


Water	Water	SAMPAs	FPGAs	Pads	ROC	T	T	Comments
FECs	ROC	dT (C)	dT (C)	dT	dT	Min	Max	
T (C)	T(C)			(C)	(C)	(C)	(C)	
17	25	3÷5	7	0.27	0.6	18	33	
19	22	3÷5	7	< 0.2	0.2	20	35	optimum

Cooling (Autodesk Inventor Nastran): simulation

Electronics water: T=19 C


ROC water: T=22 C


Air: T=23 C



Experimental and simulation results are comparable


chiller simulation







dT=0.4 K


Example of "normal" cooling





TPC cooling system








Barrel part – shorter and fixed




Full set – delivered




contract JINR-INP BSU (Minsk) – in progress delivery – 30 September 2023 operation under manual control – during beam test 2024 fully automatic control – 30 September 2024

TPC+ECAL cooling system: scheme





TPC+ECAL cooling system





TPC+ECAL cooling system





S=4x5 m2 h=2.5 m 6 racks S=1.2x3.6 m2 h=2.2 m

TPC+ECAL: power consumption


Parameter	TPC thermal stabilization	TPC cooling	ECAL cooling
N loops	60	36	10
Electronics P (kW)	1.3	16	7.5
V (m3/h)	36	8	3.24
m (kg/sec)	10	2.2	0.9
Water heat, dT	3	0	0
P1 (kW) water heat	126	0	0
P2 (кВт) racks	1	1	1
P1+P2 (kW)	127	17	8.5

1-st floor on the electronic platform: 6 racks (size 1.2x3.6 m, h=2.2 m)

TPC gas system

Gas supply





Tests - in progress (H20 and Q2 sensors are replaced)

TPC LV+HV system

LV&HV system based on CAEN rad. hard design:

(up to 2000 Gauss and 15 kRad)

- power converters A3486 AC/DC (380 V \rightarrow 48 V) -15+3 pc

- EASY3000 crates - 14+2 pc

- LV module - A3100B (8V/100A) - 48+8 pc

- LV module - A3100HBP (14V/50A) - 6 +2 pc

- HV modules -A3540P (+4kV/1mA) - 8+3 pc

- HV modules -A3540N (- 4kV/1mA) - 2+2 pc

Status:

LV+HV system: JINR-CAEN contract signed

Expected delivery date to JINR:


- September 2023

test system - tests ongoing

LV cables (halogen free, low smoke): new cable S=50 mm2 – contract signed delivery date to JINR - Feb 2023


HV cables - ordered









TPC cables and pipes integration






TPC cables and pipes integration









design – in progress ...


TPC racks (4-th floor, 8pc)





Integration TPC to MPD: tooling


















Tooling manufacture – August 2023





MPD TPC status 2022: summary





Status:

• TPC:

C1-C2 and C3-C4 cylinders - assembled **TPC** field cage assembly - Jan-Feb 2023 **TPC** vessel ready - March 2023 **TPC** service wheels (2pc) - assembled

ROC chambers

- 24 +2 spare tested Test of FE (62 cards) with ROC - preparation ongoing Flat cables (28 sets + spare) - ready FE radiators (28 sets) - narrow plates - modification in progress LVN9 stabilization boards (28 sets) - modification in progress FE power cables (28 sets) - modification in progress

- manufactured, ready Alignment pins (120 pc) **Pads alignment (calibration)** - data processing in progress

Assembly FE with ROC - procedure is ok

Test of installation ROC to TPC - move to May 2023 (will be used mock up at bld.205)

Gating Grid system (GGS) - Dec 2022

• Electronics:

FE electronics (727 cards (48%)) - ready

Rest part of FE electronics (800 cards) - will be manufactured during 2023

RCU controller - design done, prototype manufactured, tests done

Integration RCU controllers to TPC - 2023 **RCU** mass-production - 2023





MPD TPC status 2022: summary





Status of sub-systems:

DAQ:

DAQ set up #1 (FE tests at room 107) - ok!
DAQ set up #2 (FE tests at Minsk) - ok!

Gas system - tests ongoing, integration to MPD started

TPC cooling system - tender finished

HV+LV systems (CAEN) - 10% delivered, contract signed, delivery to JINR – sept 2023

Laser calibration system - UV lasers and beam distribution systems delivered, rest parts – ordered

Slow control system - integration to common TPC SC system - **not started yet ...**

Cabling and piping:

TPC cabling and piping design

TPC trays design

TPC trays manufacture

LV bars and LV cables manufacture

HV cables manufacture

Gas piping

Cooling piping

Patch panels

- in progress

- summer 2023





MPD TPC status 2022: summary





Status:

Integration TPC to MPD:

TPC racks (8pc) - layout optimization in progress

TPC rails (calculations, manufacture) - Feb 2023 -> June 2023 On critical path

rails installation to MPD - July 2023

Tooling for installation TPC to MPD:

design - finishing

tooling manufacture - Jan-July 2023 (7 month)

delivery to JINR - August 2023

TPC+ECAL cooling systems installation – up to Sept 30 2023

TPC schedule:

TPC installation to MPD Oct-Nov 2023

cabling and piping Sept-Nov-Dec 2023

MPD commissioning Jan-Feb 2024

TPC status

Thank you!