



Quality control and analysis of Si-planes FSD in the Xe-run

*Yu. Kopylov, E. Streletskaia on behalf of BM@N
collaboration*

10th Collaboration Meeting
of the BM@N Experiment at the NICA Facility

16 May 2023


Forward Silicon Detectors Configuration (BM@N 2023 – Xe run)




View of the FSD in the magnet SP-41 (working position)




Half plane view #3



View of the FSD in the magnet SP-41




Location of FSD planes in session 2023 (side OYZ)



Location of FSD planes in session 2023 (side OXY)



Planes	#0	#1	#2	#3	Total
Modules	6	10	14	18	48
Channels	7680	12800	17920	23040	53760
Area, m ²	0,035	0,073	0,102	0,132	0,307

Silicon Detector Module




DSSD and Pitch Adapter tests


Basic parameters of DSSD 640×640 for Forward Silicon Tracker



Measurement scheme of summary dark current by using first guard ring and scribing line




Summary DSSD's Dark Currents at
 $V_{bias} = 100 \text{ V}$ and $t_m = +23 \text{ }^\circ\text{C}$,
RIMST, Zelenograd





I-Vs for different measurement
scheme, $t = +20 \text{ }^\circ\text{C}$

Basic parameters of Pitch Adapter








Measurement scheme of summary leakage current




Long-term dependence of the total leakage current PA at a fixed voltage of 100 V
Average leakage current for 1 capacitor ≈
1.5 pA after 1 hour


Stages of Assembly and Testing of the Silicon Coordinate Module




$$\sigma_{\text{noise}} : C_{\text{in}} = 0 \text{ pF}, I_{\text{in}} = 0 \text{ nA}$$



$$\sigma_{\text{noise}} : C_{\text{in}} = CR_{\text{PA}}, I_{\text{in}} = I_{\text{PA}}$$



$$\sigma_{\text{noise}} : C_{\text{in}} = CR_{\text{PA}}, I_{\text{in}} = I_{\text{PA}} + I_{\text{encap}}$$









$$\sigma_{\text{noise}} : C_{\text{in}} = CR_{\text{PA}} + CR_{\text{DSSD}}, I_{\text{in}} = I_{\text{DSSD}} + I_{\text{PA}} + I_{\text{encap}}$$

FST Si module test results

module #42




Occupancy distributions in FSD Si module channels after noise suppression




Module view after US- Bonding detectors and PAs,
number of US- Bonding – 640, Ø Al wire – 25 μ m

$$1\text{ch. ADC}_{\text{p}^+} = 45 \text{ e } 1\text{ ch. ADC}_{\text{n}^+} = 42 \text{ e}$$

Module ID	Dark current (50V), nA	Mean noise (${}^+\text{p}$), ch. ADC	Mean noise (${}^+\text{n}$), ch. ADC	MPV (${}^+\text{p}$), ch. ADC	MPV (${}^+\text{n}$), ch. ADC	S/N p^+ side	S/N n^+ side	Bad channels ratio, %
42_0	3 584,00	36,93	50,76	536,20	578,89	14,09	13,32	0,55



Analysis of the work of Si-planes FSD in Xe-run



Conclusion

Eliminate dead zones (sized 128 channels) in coordinate planes

Backup slides

Conclusion

Results

+ All FSD planes worked stably in the BM@N-2023 session:

- No thermal breakdown of detectors;
- No electrical breakdown of PAs;
- Stable operation of the reading electronics;

+ According to the analysis of dark currents, the detectors received a minimal amount of radiation damage and can be used in the next session BM@N;


Plans

• Elimination of dead zones:


- Re-testing PCBs that did not pass the initial selection for installation in the module;
- Building new modules.

FST Si module test results


Cosmic test




Hits distribution





Amplitude of clusters distributions



Correlation plot



Xe run BM@N, 2023



Entries: 71413

