



MPD TPC STATUS (18.04.2023)

TPC:

- vessel assembly, ROC chambers, gating grid system



Sub-systems:

- Electronics
- LV+HV system (CAEN)
- Gas and cooling systems
- Laser calibration

Integration TPC to MPD


- Electronics platform
- Cabling and piping
- Installation TPC to MPD

Time schedule



Presented by S.Movchan

MPD TPC MAIN PARAMETERS





Item	Dimension
Length of the TPC	340cm
Outer radius of vessel	140cm
Inner radius of vessel	27 cm
Outer radius of the drift volume	133cm
Inner radius of the drift volume	34cm
Length of the drift volume	170cm (of each half)
HV electrode	Membrane at the center of the TPC
Electric field strength	~140V/cm;
Magnetic field strength	0.5 Tesla
Drift gas	90% Ar+10% Methane, Atmospheric pres. + 2 mbar
Gas amplification factor	~ 10 ⁴
Drift velocity	5.45 cm/μs;
Drift time	< 30μs;
Temperature stability	< 0.5°C
Number of readout chambers	24 (12 per each end-plate)
Segmentation in φ	30°
Pad size	5x12mm ² and 5x18mm ²
Number of pads	95232
Pad raw numbers	53
Pad numbers after zero suppression	< 10%
Maximal event rate	< 7 kHz (Lum. 10 ²⁷)
Electronics shaping time	~180 ns (FWHM)
Signal-to-noise ratio	30:1
Signal dynamical range	10 bits
Sampling rate	10 MHz
Sampling depth	310 time buckets

TPC VESSEL ASSEMBLY



Bld. 217




Service wheel with
thermal panels (12pc)



Both service wheels - assembled



ISO-6





Rods D=40 mm (24 pc) reassembled - ready
Rods D=60 mm (24 pc) – assembling in
progress, ready - June 2023

C1-C2 and C3-C4 cylinder – assembled
TPC service wheels (2pc) - assembled
HV membrane – tested
TPC field cage assembly - July 2023
TPC vessel ready – August 2023



TPC vessel assembly – in progress (see next slide)

TPC VESSEL ASSEMBLING




TPC body assembled with test rods for check TPC geometry by laser tracker AT-402 (reflector type -TBR ($R=6.35\text{ mm}$), reflector center offset $L=12.00\text{ mm}$): 2 flanges, HV electrode and C1-C2 cylinder - **miss alignment is about 1 mm**

Goal – improve miss alignment by factor x2

TPC VESSEL ASSEMBLING


Flanges and HV electrode unflatness



Flanges unflatness – about 0.5 mm

HV electrode unflatness – about 0.7 mm

Flange to flange distance



$L = (3300.5 \pm 0.5) \text{ mm}$
(nominal – 3300.0 mm)

ROC CHAMBERS AND GATING GRID SYSTEM (GGS): STATUS

Test set up for ROC certification




24 pc ROCs – tested




24 pc serial ROCs + 4 spare – **READY!**

Test set up for pads calibration




Leica MS60 - 1 second resolution
Leica AT960 +/-10 mkm +5 mkm/m
Leica AT403 +/-15 mkm +6 mkm/m
Scanner AS1+AT960 +/-50 mkm

Pad plane unflatness: example



Check pads geometry



Full set of ROC alignment marks



Summary:

- measurements to do for all ROCs
- **calibration** of ROC marks and 3968 pads respect to ROC
- “reference hole” - **in progress**

ROC gating grid system: test set up



Pulse rise time
- 500 ns, **OK!**




Mass-production – **in progress**
Delivery to JINR – **Sept 2023**

TPC SUB-SYSTEMS: ELECTRONICS

Production version of the FE card:




TPC FE cards production status




15 ROCs chambers can be completed
(from 24 ROCs)

DAQ prototype:
62 FE cards, RCU prototypes,
ROC, 2pc LVDBs, server interface
board - **tests ongoing**




1. RCU prototypes
2. FECs on the ROC (62 pc)
3. LV power supply
4. DCU card connected with RCUs via fibers
5. Readout server

RCU-64 controller:
testing with FEE



LVN9 stabilizer





FE radiators
(water cooling)



60 pc LVN9 were send back to Minsk:
- modification connection of power cables to LVN9 - **in progress**
- modification of LVN9 output voltages to FECs - **in progress**
- test of LVN9 with cooling radiator under full load (analog – 70 A, digital – 50 A) – **in progress**

- **967 FECs** of 1500 were produced.
- Tests of the FEC basic functionality were shown the target characteristics (noise and stability).
- Testing of the readout system for one **ROC** is **ongoing**.

TPC SUB-SYSTEMS: LV+HV (CAEN)



LV&HV system based on CAEN rad. hard design:

(up to 2000 Gauss and 15 kRad)

- power converters A3486 AC/DC (380 V -> 48 V) – 15+3 pc
- EASY3000 crates – 14+2 pc
- LV module - A3100B (8V/100A) – 48+8 pc
- LV module - A3100HBP (14V/50A) – 6 +2 pc
- HV modules –A3540P (+4kV/1mA) – 8+3 pc
- HV modules –A3540N (- 4kV/1mA) – 2+2 pc

Status:

LV+HV system: JINR-CAEN *contract signed*

Expected delivery date to JINR: *August 2023*

test system – *tests ongoing*

LV cables (halogen free, low smoke):

S=50 mm² – **delivered**

HV cables - ordered



TPC SUB-SYSTEMS: GAS AND COOLING

Gas system (Ar/CH₄, 90:10)

Gas supply





Racks

TPC volume imitator




Tests - in progress
(H₂O and Q₂ sensors are replaced)


Water cooling system




contract JINR-INP BSU (Minsk) – in progress
delivery – 30 September 2023
operation under manual control – during beam test 2024
fully automatic control – **30 September 2024**




Full set of panels – delivered



MPD hall



S=1.2x3.6 m²
h=2.2 m



Bottom cooling plates





Set of top cooling plates



Cu tube Din - 3.16 mm
Plates thickness - (4+4) mm

COOLING PROTOTYPE

T sensor based on Pt100




7 sensors





7 sensors

Cooling simulation
(Autodesk inventor Nastran)




Electronics water:
T=19 C
ROC water: T=22 C
Air: T=23 C

Experimental and simulation
results are compatible




COOLING PROTOTYPE: RESULTS

Set up



ROC + pad sensors




FE card sensors



LV power



Chiller




Air: T=23 degree (C)

Water FECs T (C)	Water ROC T(C)	SAMPAs dT (C)	FPGAs dT (C)	Pads dT (C)	ROC dT (C)	T Min (C)	T Max (C)	Comments
17	25	3÷5	7	0.27	0.6	18	33	
19	22	3÷5	7	< 0.2	0.2	20	35	optimum





SERIAL COOLING SYSTEM: STATUS

TPC system pressure with water column height

Hydraulic pressure drop
for ROC chambers




$$dP \leq 0.5 \text{ atm}$$




Water velocity: (1.5-2.5) m/s

Systems parameters optimization by
calculations – in progress




TPC SUB-SYSTEMS: LASER CALIBRATION

Scheme for 1/2 TPC





- Laser “planes” - 4
- Micro-mirrors bundles per plane - 4
- Beams from micro-mirrors bundle - 7
- Laser “tracks” ($N = 112 \times 2$) - 224

micro-mirror
bundles



TPC



Laser beam splitter



Laser beam monitor



TPC laser calibration for electron drift velocity (root version)

MPD


Space-charge distortion in TPC volume change the electron drift velocity ($\leq 1 \text{ sec.}$)— corrections are needed.

Bychkov A.

Reasons:

- Variation in drift velocity caused by gas mixture, temperature, pressure and electric field variation.
- Radial inhomogeneities of magnetic and electric field.
- Space charge distortions due to high multiplicity in nucleus-nucleus collisions.
- TPC misalignment in the magnet and existence of the global $E \times B$ effect.

Reconstructed hits of the laser grids



TPC electron drift velocity calibration (standalone fast version)

MPD

Test for drift velocity correction



Bychkov A.

Source data

- True drift velocity = 5.5 cm/us
- Simulated drift velocity = 5.4 cm/us
- Test on laser grid itself

Red — measured position


Black — corrected position




/ 10

NICA-MPD-PLATFORM (NMP)

Common view



TPC equipment



TPC + ECAL
cooling

Design and integration –
in progress ...

MPD ELECTRONIC PLATFORM


TPC equipment in racks on the 4th floor

F4-R1 (empty)	F4-R2 LV	F4-R3 LV	F4-R4	F4-R5	F4-R6 (LV)	F4-R7 (LV)	F4-R8 (empty)
47	47	47	47	47	47	47	47
46	46	46	46	46	46	46	46
Cable organizer	Cable organizer	Cable organizer	Cable organizer	Cable organizer	Cable organizer	Cable organizer	Cable organizer
45	45	45	45	45	45	45	45
Patch Panel Fiber	Patch Panel Fiber	Patch Panel Fiber	Patch Panel Fiber	Patch Panel Fiber	Patch Panel Fiber	Patch Panel Fiber	Patch Panel Fiber
44	44	44	44	44	44	44	44
Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg	Aruba 3810M 24G (146W) 6kg
43	43	43	43	43	43	43	43
Система GATE	A3486 Nr1 (380VAC-40VDC)	A3486 Nr4 (380VAC-40VDC)	A3486 Nr7 (380VAC-40VDC)	A3486 Nr8 (380VAC-40VDC)	A3486 Nr9 (380VAC-40VDC)	A3486 Nr12 (380VAC-40VDC)	A3486 Nr15 (380VAC-40VDC)
40W x 12 камер x 500W	3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	Питание SC для всех крайних EASY	3kW, max.4kW 380V/15A 30kg	Питание+48V 2x крайних EASY 3000 (Hv)	3kW, max.4kW 380V/15A	max.1.5kW 380V/15A
40	40	40	40	40	40	40	40
220V/10A	30kg	30kg	380V/15A, 3 kW (max. 4 kW), 30kg	30kg	30kg	30kg	30kg
39	39	39	39	39	39	39	39
20kg							
38	38	38	38	38	38	38	38
Crate EASY 3000 Nr1	Crate EASY 3000 Nr4	Crate EASY 3000 Nr6 (Hv)	Crate EASY 3000 Nr8 (Hv)	Crate EASY 3000 Nr9 (Hv)	Crate EASY 3000 Nr12	Crate EASY 3000 Nr15	Crate EASY 3000 Nr15
Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486
37	37	37	37	37	37	37	37
Система GATE							
40W x 12 камер x 500W							
36	36	36	36	36	36	36	36
220V/10A							
35	35	35	35	35	35	35	35
20kg							
34	34	34	34	34	34	34	34
42.5kg	42.5kg	42.5kg	42.5kg	42.5kg	42.5kg	42.5kg	42.5kg
33	33	33	33	33	33	33	33
32	32	32	32	32	32	32	32
31	31	31	31	31	31	31	31
30	30	30	30	30	30	30	30
Система SPECTRA	A3486 Nr2 (380VAC-40VDC)	A3486 Nr5 (380VAC-40VDC)	Crate SC для LVN9	Crate SY4527 (Hv)	A3486 Nr10 (380VAC-40VDC)	A3486 Nr13 (380VAC-40VDC)	Система GATE
1050W	3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	300W	700W, max. 1.2kW	3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	40W x 12 камер x 500W
27	27	27	27	27	27	27	27
220V/15A	30kg	30kg	220V/10A	220V/10A	30kg	30kg	220V/10A
26	26	26	26	26	26	26	26
50kg			5kg	(8 модулей x 12chx96ch=1.5V/1mA +			20kg
25	25	25	25	25	25	25	25
Crate EASY 3000 Nr2	Crate EASY 3000 Nr5	Система модульного покрытия	Система модульного покрытия	Система модульного покрытия	Crate EASY 3000 Nr10	Crate EASY 3000 Nr13	Система GATE
Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486
24	24	24	24	24	24	24	24
45kg			Питание LVN9 - 48 шт.]	45kg			40W x 12 камер x 500W
23	23	23	23	23	23	23	23
22	22	22	22	22	22	22	22
Сист. SPECTRA			Crate VMER100/11	Сист. SPECTRA			220V/10A
21	21	21	21	21	21	21	21
42.5kg	42.5kg	42.5kg	1.1kW, max. 2.5kW	42.5kg	42.5kg	42.5kg	20kg
20	20	20	20	20	20	20	20
Модуль термометрии NI			220V/15A	Crate VMER100/11			
19	19	19	19	19	19	19	19
200W			30kg	1.1kW, max.1.5W			
18	18	18	18	18	18	18	18
220V	Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA	220V/15A	Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA
17	17	17	17	17	17	17	17
5kg				30kg			
16	16	16	16	16	16	16	16
A3486 Nr3 (380VAC-40VDC)	A3486 Nr6 (380VAC-40VDC)	A3486 Nr6 (380VAC-40VDC)		A3486 Nr11 (380VAC-40VDC)	A3486 Nr14 (380VAC-40VDC)	Сист. SPECTRA	Сист. SPECTRA
15	15	15	15	15	15	15	15
3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	Сист. SPECTRA	3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	3kW, max.4kW 380V/15A	500W
14	14	14	14	14	14	14	14
TPC Laser system synchronization	30kg	30kg			30kg	30kg	220V/15A
13	13	13	13	13	13	13	13
200W, 220V			Crate NIM	Сист. SPECTRA			50kg
12	12	12	12	12	12	12	12
5kg	Crate EASY 3000 Nr3	Crate EASY 3000 Nr6	610W, max. 1.15kW	Crate EASY 3000 Nr11	Crate EASY 3000 Nr14	Crate EASY 3000 Nr14	
11	11	11	220V/10A	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	Питание + 48V Seperts от A3486	
10	10	10	10	10	10	10	10
TPC HV membrane - 30kV			30kg	Crate NIM			
9	9	9	9	9	9	9	9
350W				610W, max. 1.15kW	220V/10A		
8	8	8	8	8	8	8	8
220V	42.5kg	42.5kg		30kg	42.5kg	42.5kg	
7	7	7	7	7	7	7	7
7kg			Сист. SPECTRA				Модуль термометрии NI
6	6	6	6	6	6	6	6
							200 W
5	5	5	5	5	5	5	5
Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA	Сист. SPECTRA	220V
4	4	4	4	4	4	4	4
							5kg
3	3	3	3	3	3	3	3
2	2	2	2	2	2	2	2
1	1	1	1	1	1	1	1

TPC CABLING AND PIPING

W side: cooling and gas pipes scheme

100 мрyд стадилизациу +2 мрyд TPC
 \varnothing 32x47(штыцер) mm




TPC list of cables and pipes

List of cables and pipes																	
	Purpose	Diameter, mm	14	12	10	8	6	4	2	1	3	5	7	9	11	13	
			Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	Qty	
EDTC	Data cable	3	0	6	12	18	24	30	36	42	48	54	60	66	72	78	
ESNC	Sensor cable	9,4	0	3	6	9	12	15	18	21	24	27	30	33	36	39	
EPWC	Power cable	14,7	0	3	6	9	12	15	18	21	24	27	30	33	36	39	
ESRL	Service cable(1)	3x13	0	3	6	9	12	15	18	21	24	27	30	33	36	39	
EWCT	Watercooling tubes	~20	0	2	4	6	8	10	12	14	16	18	20	22	24	26	
EACT	Air cooling tubes for FE and BCK	~20	0	2	4	6	8	10	12	14	16	18	20	22	24	26	
TSGC	Signal	13	10	20	30	40	50	60	70	80	90	100	110	120	130	140	
THVC	HV	8,5	0	4	4	8	8	12	12	16	16	20	20	24	24	28	
TLVC	LV Cable	13	1	1	2	2	3	3	4	4	5	5	6	6	7	8	
TUTC	UTP	6	1	1	2	2	3	3	4	4	5	5	6	6	7	8	
TTRL	Trigger (OR)	10	2	2	4	4	6	6	8	8	10	10	12	12	14	16	
TGST	Gas Pipes	12	2	2	4	4	6	6	8	8	10	10	12	12	14	16	
TPC gas system																	
TGTT	Purge TPC (in/out)	40	0	0	0	0	0	0	0	1	1	1	1	1	1	1	
LV																	
TLPC	LVDB: low-voltage cable supply	12	0	8	8	16	16	24	32	32	32	32	40	40	48	48	
TLSC	LVDB: sense wire	2,5	0	4	4	8	8	12	16	16	16	16	20	20	24	24	
TCPC	Controller: low-voltage cable supply	12	0	2	2	4	4	6	8	8	8	8	10	10	12	12	
TCSC	Controller: sense wire	2,5	0	1	1	2	2	3	4	4	4	4	5	5	6	6	
TLCC	LVDB: slow control cable	9	0	2	2	4	4	6	8	8	8	8	10	10	12	12	
DAQ																	
TDCC	Controller: slow control	7	0	2	2	4	4	6	8	8	8	8	10	10	12	12	
TDOD	Controller: DATA CSFP	opt. 3,3	0	1	1	2	2	3	4	4	4	4	5	5	6	6	
TDTD	Controller: data and trigger/ sync SFP+	opt. 3,3x1,8	0	1	1	2	2	3	4	4	4	4	5	5	6	6	
TDTC	Controller: trigger	6	0	1	1	2	2	3	4	4	4	4	5	5	6	6	
TDRC	Controller: Reset	6	0	1	1	2	2	3	4	4	4	4	5	5	6	6	
TDSC	Controller: Sync	6	0	1	1	2	2	3	4	4	4	4	5	5	6	6	
TDOD	Reserve cables CSFP	opt. 3,3	0	1	1	1	1	1	2	2	2	2	2	2	2	2	
TDSD	Reserve cables SFP+	opt. 3,3x1,8	0	1	1	1	1	1	2	2	2	2	2	2	2	2	
ROC chamber																	
TRAC	for ROC: HV power supply for anode sections	4,1	0	0	4	4	8	8	8	8	12	16	16	20	20	24	
TRBC	for ROC: HV electrode adjusting supply	4,1	0	0	1	1	2	2	2	2	3	4	4	5	5	6	
TRHC	for ROC: HV locking grid	4,1	0	0	2	2	4	4	4	4	6	8	8	10	10	12	
TRCC	for ROC: cameras electrode (cathode), test signal	4,1	0	0	1	1	2	2	2	2	3	4	4	5	5	6	
TRSC	from ROC: signal cable (anode)	4,1	0	0	4	4	8	8	8	8	12	16	16	20	20	24	
Sensors																	
TSSC	Temperature sensor cable P100	8	0	0	3	3	6	6	6	6	9	12	12	15	15	18	
TSPC	Cables from pressure sensors on pipes cooling + stabilization	7,8	0	0	4	4	8	8	8	8	12	16	16	20	20	24	
TSYC	Cables from temperature sensors on pipes cooling + stabilization	7,8	0	0	4	4	8	8	8	8	12	16	16	20	20	24	
HV TPC central membrane																	
THEC	Central HV electrode TPC	8	0	0	0	0	0	0	0	0	1	1	1	1	1	1	
THVC	low-voltage cable input for resistors (centr), HV electrode	10	0	0	0	0	0	0	0	0	1	1	1	1	1	1	
Thermalstabilization																	
TTOT	external thermal screen stabilization pipes	32	0	0	2	2	2	4	4	4	6	6	7	8	8	10	
TTTT	and Thermal Shield Stabilization Pipes	32	0	0	0	0	1	2	2	2	2	2	2	3	4	4	
TTIT	inner thermal shield stabilization pipes	32	0	0	2	2	2	2	2	2	2	2	2	2	2	2	
TTST	Pipes stabilization ROC chambers housings	32	0	0	0	0	0	0	0	0	0	2	2	2	2	2	
TTFT	TPC flange stabilization pipes with spikes	32	0	0	0	0	0	0	1	3	4	4	4	4	4	4	
TTST	Stabilization pipes FE SAMPA	32	0	4	4	6	8	9	12	12	15	16	17	20	20	24	
Cooling (12 loops)																	
TLCT	Cooling pipes LVDB, controllers & FE FPGA	32	0	0	0	1	2	2	2	2	2	2	3	3	4	4	
TPC laser system																	
TLVC	Cable for WEB camera control system floor laser beam	7	0	0	1	1	1	1	1	1	1	2	2	2	2	2	
TPC gas system																	
TGST	Purge of C1C2 and C1C4 (input/output)	12	0	0	0	0	0	0	0	0	0	0	1	1	1	1	
Hydraulic actuators																	
TSGC	Position centers hydraulic cylinder	6	0	4	4	4	4	4	4	4	4	4	4	4	4	4	

TPC CABLING AND PIPING

Integration ...

Structures for
cables and pipes
fixation



Structure design - **in progress**


Prototype for cabling and piping







TPC+TOF+ECAL cabling – **in progress**
Piping – not started yet

TOOLING FOR INSTALLATION TPC TO MPD


Bld. 217



Bld. 217 (MPD)



4 units for adjustment X, Y, Z



Design under
optimization,
Prototype 1:5 –
June 2023

Tooling manufacture –
July 2023-Feb 2024
Delivery to JINR –
Spring 2024

TIME SCHEDULE

Status:

TPC assembling:

Field cage assembly	- July 2023
HV tests	- August 10 2023
TPC vessel ready (glue by epoxy)	- August 30 2023
Laser beams position measurements	- Sept 2023
TPC vessel tightness measurements	- Oct 2023
24 ROC chambers installation	- Nov-Dec 2023
TPC tests: laser tracks and cosmic test	- Jan-Sept 2024

Integration TPC to MPD:

TPC racks (8pc) + cabling	- autumn 2023-2024
---------------------------	--------------------

TPC rails (2pc manufacture and delivery)	- Oct 30 2023	on critical path !!!
--	---------------	----------------------

Rails installation to ECAL support structure	- Nov 2023
--	------------

Tooling for installation TPC to MPD:

Design optimization + prototype 1:5	- June 2023
Tooling manufacture	- July 2023 – Feb 2024 (8 month)
Delivery to JINR	- Spring 2024

TPC+ECAL cooling systems: FE cooling	- Nov 2023
commissioning	- Sept 30 2024

TPC installation to MPD	- Oct 1-Nov 30 2024
MPD commissioning	- Jan 10 - Feb 2025

Thank you !