Cryogenic system of SPD

Speaker:


Yurii Bespalov

Leader of cryogenic system of SPD:

PhD Dr. Nikiforov Dmitry

Outline


- 1. Cryogenic system
- 2. Helium system
- 3. Cryogenic equipment
- 4. Nitrogen system
- 5. Cryogenic system control
- 6. Steps of creation
- 7. Conclusions






Andrey Ponomarev


Cryogenic system




Helium system

Control cryostat










Helium liquefier


	Operating parameters	Unit
1	Cooling capacity	140 l/h
2	Temperature of outlet flow from the SPD	4.3 K (1.05 bar)
3	Temperature of inlet flow from the SPD	4.5 K (1.15 bar)
4	Hydraulic resistance of the SC coil	0.1 bar
5	Cold weight	3800 kg
6	Maximum pressure in coil	5 MPa
7	Maximum heat load	100 W
8	Equipment Requirement	Maximum reliability, energy efficiency, compactness, automatic mode
9	Interval of repair/regulatory work of the plant	Not more than once a year




Technical platform of cryogenic equipment







Cryogenic tanks platform



- 1 Two storage tanks for LN2;
- 2 Storage tank for LAr;
- 3 Storage tank for LCO2;
- 4 Evaporator for LAr;
- 5 Cryogenic pumps;
- 6 Equipment room.


Pipelines

Cryogenic line:


LN2 - 120 m (rigid tube) LN2 - 40 m (flexible tube)

Warm line:

Ar - 120 m (rigid tube) N2 - 120 m (rigid tube) CO₂ - 120 m (rigid tube)



Cryogenic system control



Other subsystems

Vacuum system






Pumping station with two foreline pumps and turbomolecular pump



Pneumatic system



Steps of creation																								
	2022			2023			2024				2025				2026				2027					
SPD		II	III	IV	I	II	III	V	I	II	Ш	IV	I	II	Ш	IV	I	II	Ш	IV	I	II	Ш	IV
Cryogenic plant																								
Helium pipeline																								
Nitrogen system																								
Vacuum system																								
Pneumatic system																								
Cryogenic system																								
control																								



Contract execution



Commissioning



Conclusions:

- ➤ The type of SPD magnet and the type of cryogenic plant was determined.
- The location of cryogenic tanks, their volumes and gas flow rates for SPD were determined.
- ➤ The cooling capacity, mass flow rate and working cycles of the cryogenic plant are calculated.
- ➤ The development of technical tasks for a cryogenic plant and a platform for cryogenic storage tanks is in the active phase.
- > The work is carried out according to the plan.



Thank you for your attention!





