

MPD Data Acquisition System Status

Andrey Shchipunov
MPD DAQ working group

A. Baskakov, S. Bazylev, A. Egorov, A. Fediunin, I. Filippov, S. Kuklin,
A. Shchipunov, A. Shutov, I. Slepnev, V. Slepnev, N. Tarasov, A. Terletskiy

Joint Institute for Nuclear Research



XII Collaboration Meeting of the MPD Experiment
at the NICA Facility



MPD DAQ Design Goals

Properties

Reliable data transfer. Pipeline operation with sync and async stages.
Extensive diagnostics in hardware and software. Monitoring, logging.
Data integrity check on all levels. CRC, sequence numbers, FEC.
Fault tolerant, Highly available. Fast self recovery after SEU events.
Distributed, scalable, extendable. Based on open and industry standards.
Flexible architecture. Partitioning for independent subsystem operation.


Operation Modes

Multiple hardware trigger classes
Uncompressed, full raw data during MPD commissioning
Large calibration data events at low trigger rate
High multiplicity events from central collisions at planned trigger rate

DAQ in numbers


Up to 7 kHz trigger rate, over 1 MB event size to storage device
From 5 to 30 GB/s uncompressed raw data rate from readout cards to FLP
Up to 200 PB per year of raw data

MPD DAQ Architecture



TTVXS — VXS Switch Board

TTVXS is a Time, Trigger and Management module for VXS crate



IPMI mezzanine board

- Clock, timestamp and trigger distribution to VXS payload boards: backplane FE-Link protocol
- 4 SFP+ sockets for Detector Readout, Trigger Distribution and Clock & Timing connections
- Reference frequency and timestamp provided by White Rabbit Network or FE-Link (with CRU-16)
- Additional clock and trigger interface by FMC (VITA-57) card slot – integration with other systems

Status: 20 boards ready, basic functions implemented

IPMI mezzanine board

- IPMI (Intelligent Platform Management) function for automatic topology discovery, module status monitoring and control, firmware update

Status: basic functions implemented, improvements ongoing

TDC72VHL — Multihit 25 ps Timestamping TDC




TDC72VHL board performs time-stamping of discrete signals (hits). It is based on HPTDC chip. Hit timestamps are kept for 104 us in ring type memory.

Number of Channels	72
Input Signal	LVDS
Input Impedance	100 Ohm
Input Differential Voltage	25 mV min
Input Connector	CXP Interconnect System
Time Resolution with INL	~25 ps
Data Transfer Interface	1Gb/s Ethernet
Synchronization Interface	FE-Link over VXS

MPD TOF Test Stand

Test stand in building 42 for checking DAQ electronics and TOF modules.

On photo 4 VXS crates used for testing several TOF modules. In each VXS crate 1 TTVXS and 14 TDC modules are installed.




CRU-16

Common Readout Unit for 16 DRE boards

- FE-Link interface to DRE boards - multi-gigabit duplex serial synchronous interconnect with deterministic latency. Provides clock and trigger information for downstream boards and receives raw data stream
- 4 GB SO-DIMM DDR3 memory for data buffers. Decouples realtime hardware data flow from high latency software data receivers
- 4 QSFP downlink sockets for 16 Detector Readout boards connections grouped by 4
- 1 QSFP uplink socket for 40 Gb Ethernet data transfer
- 3 SFP sockets for Trigger Distribution, Clock & Timing
- Management mezzanine board
- Timing synchronization by White Rabbit network

Status


- Hardware manufactured, all module components tested
- Software firmware parts ready. FE-Link designed and tested on prototype
- Control software under development



ADC64ECAL, ADC64s2-v5 — Waveform digitizers




ADC64ECAL under test, active air cooling



ADC64ECAL under test, passive air cooling



ADC64* board characteristics

	ADC64ECAL	ADC64s2-v5
<i>Number of channels</i>	64	64
<i>Sample rate</i>	62.5 MS/s	62.5 MS/s
<i>Resolution</i>	14 bit	14 bit
<i>Power consumption</i>	< 15 W	< 20 W
<i>Magnetic field tolerance</i>	by design	no
<i>Radiation hard DC/DC</i>	no	no




ADC64s2-v5 assembly (FHCAL)

MPD ECAL Test Stand



Common Readout (and everything else) unit

CRU-16



Front-End (FE link)

“Variable-speed Synchronous Ethernet”. Byte-oriented, 8b/10b Ethernet like encoding and framing
Maximum data rate: 2.5 Gb/s VXS backplane (TTVXS), 8 Gb/s (CRU-16) with commercial QSFP fiber-optical transceivers.
DRE clock synchronized to CRU with digital PLL. Short fixed cables – one time delay calibration.
Timestamps, trigger, data readout, control over same link
No TCP-IP stack complexity in DRE. Simple FPGA code with fail-safe FSM and data pipelines to mitigate SEU events.

Aggregation «switch» (CRU-16 core)

Not an Ethernet switch. Fixed traffic directions: left-right or right-left only. Connects to DAQ network with 10G Ethernet, UDP-IP.
Large FPGA on board running White Rabbit and service CPUs
Extensive diagnostics: hardware histograms, RAM-based multichannel counters
Use speed translation FIFOs. Arbitrated crossbars. DDR3 SDRAM onboard (packet buffers)
Future: hardware event merging for connected DRE boards

DAQ Electronic Modules Production

Product	Required boards						Manufactured and Tested Q1 2023	Progress
	ECAL	FHCAL	FFD	TOF	TPC	Trigger Distrib.		
TDC72VHL	—	—	10	196	—	—	219	106 %
TTVXS	—	—	2	14	—	4	20	100 %
ADC64-ECAL	600	—	—	—	—	—	630	105 %
ADC64S2 v5	—	10	—	—	—	—	10	100 %
CRU16	38	2	—	1	2	1	45	102 %

TDC72VHL, TTVXS status

- Hardware ready 100%
- Firmware with basic functions tested on TOF stand
- Software ready
- "FE-Link over VXS" firmware under development


ADC64 family status

- Hardware manufactured
- Tested on stands and BMN
- Refactoring monolithic to modular design (firmware and software) in progress.

CRU-16 status

- Hardware manufactured
- All on-board components tested
- Some firmware parts ready
- FE-Link designed and tested on prototype
- Control software under development

MPD DAQ Network



MPD DAQ Modular Data Center

2020-2021: Delivery, installation, testing
June 2021: Put in operation

2nd - Control Room

1st - Data Center



MPD DAQ Data Center



MPD DAQ Data Center Infrastructure



- Entrance Area
- Automatics Rack



- Rack power switches: 2 independent lines
- Battery backup: 15 minutes at 100% load
- Main Switchboard: 110 kW input power



Quad Precision Air Conditioners
N+1 redundancy

- Maximum total rack power with N+1 redundancy: 50 kW
- Maximum measured rack power with installed hardware: 26 kW

MPD DAQ Control Room



Thank you!