
# **Status of Forward Hadron Calorimeter (FHCal)**

A.Ivashkin Institute for Nuclear Research RAS, Moscow on behalf of the FHCal group

- FHCal overview;
- FHCal modules;
- FHCal readout;
- FHCal in trigger
- Installation to MPD

# **FHCal in MPD**




- <u>Two arms of hadron calorimeter</u> at opposite sides in forward regions.
- At the distance 3.2 meters from the interaction point.
- Available acceptance corresponds to pseudorapidity 2.0<η <5.0</li>


- FHCAL consists of 2x44 modules.
- ~1x1 m<sup>2</sup> each part.
- Beam hole 15x15 cm<sup>2</sup>.
- Lead/scintillator sampling calorimeter.
- Longitudinal segmentation;
- Light readout- WLS-fibers;
- 7 sections/photodetectors in each module.

# **Tasks of FHCal :**

- a) The centrality of the collision;
- b) The reaction plane orientation;
- c) Minimum bias trigger;
- d) Physics in forward rapidity?

Centrality: 2D-Fit of energy distributions in FHCal modules






# **FHCal modules**

- All (90+spare) FHCal modules are assembled and tested with cosmic rays.
- Modules are ready for the delivery at MPD site.
- Mini-FHCal is operating now at INR.








#### The activities with modules:

- Calibration with cosmic muons;
- Development of readout;
- Development of FHCal trigger;
- Development of Detector Control System;
- Monitoring system.

#### **Readout electronics (FEE)**

**MPPC**: new type S14160-3010PS **Photodetectors – MPPCs;** size – 3x3 mm<sup>2</sup>; two-stage amplifiers; pixel -10x10 μm<sup>2</sup>; PDE~18%. HV channels;





#### **100** units of FEE were produced and tested.

Two PCBs in each module with:

7 photodetectors ;

LED calibration source.




## **ADCs for FHCal**



FPGA based 64 channel ADC64 board, 62.5MS/s (AFI Electronics, JINR, Dubna).

### **Bench for ADC tests**






**5 ADCs for each part of FHCal** 

- > All 10 ADC boxes were produced last year.
- > All ADCs were tested this year at JINR.
- > 4 ADCs were repaired during the tests.
- > All ADCs are ready for installation.


#### **FHCal readout and control**

#### **FHCal arm**



Both FHCal arms have the same readout scheme.

## **FHCal cabling**




#### **Detector Control System (DCS)**


**DCS Tasks:** 

- Control of HV at photodetectors (MPPC's);
- Temperature control of photodetectors;
- Compensation of temperature drift of MPPC gain;
- Monitoring of MPPC gain with stabilized light source.


#### Status of DCS:

- It is practically fully operational;
- > Further improvements of functionality are going on.






## **FHCal in trigger**



## Scheme of FHCal trigger




Dependence of trigger efficiency on the configuration of modules (Au-Au 11 GeV).

## Preparations for FHCal trigger



- Adders of analog signals from individual modules were produces for full FHCal.
- The configuration of modules in trigger would depend on FEE and correlation noises. Flexible configuration is to be developed.

#### Dependence of trigger noise on energy threshold




#### 12-channels signal adders





All adders are working. The noises are under tests.

#### It seams that 3 MeV threshold is safe for trigger.

## **Energy calibration with cosmic nuons**









- The energy calibration is planned in self-triggering mode (without external muon trigger).
- > The different geometries of muon tracks are to be considered.
- The selection of different muon tracks can be done by requiring the coincidence of muon signals in FHCal modules and longitudinal sections.
- A few versions of energy calibration is under development (with/without correction to pass length).

## FHCal integration to MPD (ADC readout)




Two halves of FHCal.

ADC boxes are placed at the lateral sides of FHCal support




ADC cooling with compressed air is planned. 5 pipes from each side are to be available!


# **Mechanical support (main elements)**



**Basket of FHCal modules** 




et pole




**Outer table** 

- Design of all elements was finished!
  - The production starts now!


# Assembling of FHCal modules in basket



# FHCal installation into magnet pole



# Alternative way of FHCal installation from outer side of magnet pole



# Summary

- > All FHCal modules were tested and are ready for delivery at MPD site.
- FEE was produced and tested.
- > Detector Control System is ready and is improved permanently.
- Energy calibration procedure is optimized.
- FHCal trigger is under development. Flexible configuration of modules is considered.
- The design of mechanical platform is finished. The production starts now!

- We plan to start the calorimeter assembling at MPD site in the beginning of 2024.
- The space an some infrastructure for FHCal assembling must be available!

# Thank you!