

APPROVED

JINR DIRECTOR

" _____ "202г.

PROJECT PROPOSAL

Opening/renewal of a research project/subproject of the large research infrastructure project within the Topical plan of JINR

1. General information on the research project of the theme/subproject of the large research infrastructure project (hereinafter LRIP subproject)

1.1 Theme code / LRIP

02-1-1065-2007/2026

1.2 Project/LRIP subproject code (for extended projects)

02-1-1065-1-2011/2024

1.3 Laboratory

VBLHEP

1.4 Scientific field

Large research infrastructure project

1.5 Title of the project/LRIP subproject

Nuclotron-NICA

1.6 Project/LRIP subproject leader(s)

A.V. Butenko
H.G. Khodzhbagiyan

1.7 Project/LRIP subproject deputy leader(s) (scientific supervisor(s))

Scientific leader: I.N. Meshkov

2 Scientific case and project organization

2.1 Annotation

The main goals of the NICA project are the design and construction of the complex of accelerators, collider and physics experimental facilities at extracted and colliding ion beams aimed at studying dense baryonic matter and the spin structure of nucleons and light ions, and at carrying out applied and innovation projects.

To meet these goals the NICA complex will include the following main elements:

- injection complex including cryogenic heavy ion source KRION of the electron string type, source of polarized proton and deuteron beams, modernized linear accelerator LU-20, new linear heavy ion accelerator HILAC, new light ion accelerator LILAC,
- superconducting synchrotron Booster,
- modernized superconducting synchrotron Nuclotron,
- collider consisting of two superconducting rings with two interaction points,
- transport channels for heavy and light ions, polarized beams, experimental stations for innovation and applied researches and required infrastructure.

Besides that, the project realization presumes required development of the VBLHEP cryogenic complex, development of the system for management and development of the laboratory infrastructure.

In the frames of the Seven-year plan for the development of JINR for 2024–2030 the R&D, prototyping, testing, magnet production for the “new” Nuclotron ring are providing.

2.2 Scientific case (aim, relevance and scientific novelty, methods and approaches, techniques, expected results, risks)

The aims of the Nuclotron-NICA project are:

- commissioning of the NICA complex objects at basic configuration of the collider equipment,
- prolongation of the experiments at fixed targets with heavy ion and light nuclei polarized beams,
- start the experiments at colliding beams,
- R&D, prototyping, testing, pre-serial magnet production for the “new” Nuclotron ring.

The elements of the complex are created on the basis of the following document approved on December 28, 2018:

TECHNICAL PROJECT OF THE OBJECT "NICA COMPLEX"

Section: TECHNICAL SPECIFICATION (PASSPORT)

OF THE "NICA COMPLEX" OBJECT

available at the web-site https://nica.jinr.ru/documents/TDR_spec_Fin0_for_site_eng.pdf.

Specifications of the objects developing or creating in the frame of the Nuclotron-NICA project are presented in the following chapters:

2. Accelerator unit
6. Innovation unit
- 8.2. Cryogenic infrastructure
- 8.4. High-tech assembly and testing line of SC magnets

To meet the project goal one plans the development and carryout works on of the existing infrastructure of the VBLHEP accelerator complex: HILAC, Booster, Nuclotron, beam transport lines in bldg. 1, bldg. 205 and new building 17 and other systems and new equipment required for the NICA collider commissioning at project equipment configuration in 2027.

Before the project completion, the commissioning of the following elements is scheduled:

- beam transport line from the Nuclotron to collider,
- the collider at basic configuration of the equipment.

The works aimed to creation of the light ion linear accelerator LILAC will be prolonged.

Delay from the schedule of the project during 2021 – 2024 is caused mainly by delay with delivery of the engineering equipment of the collider building and equipment of the collider itself.

Until December 2023, General Contractor of the collider building construction was the Strabag company from Republic of Austria. A trilateral agreement between JINR and two companies - Strabag and Tavrida Energostroy - on assignment of rights and transfer of obligations is being concluded. Tavrida Energostroy will be the new General Contractor. That agreement must be completed in December 2024.

The undelivered equipment of the collider is under construction at Russian companies.

The problem with transportation of the LILAC equipment from Germany is not resolved yet. To provide the experimental program with polarized beams the works for performance improvement of the existing accelerator LU-20 are carrying out.

The collider commissioning at the project configuration depends on delivery of a few systems. However these systems are not critical for the collider operation at the basic configuration with colliding heavy ion beams up to Bi^{+83} at the luminosity not less than $L = 10^{24} \text{ cm}^{-2} \text{ s}^{-1}$ and energy from $\sqrt{s_{\text{NN}}} = 4 \text{ GeV/u}$.

Commissioning of the collider will be provided in the following stages:

- experiments with circulating heavy ion beams at the kinetic energy up to 2 GeV/n with internal target and colliding beams – 2025,
- commissioning of the beam cooling systems, increase of the stored beam intensity 2026,
- gradual increase of the colliding beam energy and luminosity – 2027.

Funding profile and control of its realization are provided using specialized databases ADB2 and NICA EVM.

2.3 Estimated completion date

2027

2.4 Participating JINR laboratories

DLNP, MLIT

2.5. Participating countries, scientific and educational organizations

Presented in the Topical plan 2024 at the pages 21 – 24

3. Manpower

3.1. Manpower needs in the first year of implementation

No. No n/a	Category of personnel	JINR staff, amount of FTE	JINR Associated Personnel, amount of FTE
1.	Research scientists	54 (50,8)	3 (3)
2.	engineers	245 (240,38)	
3.	specialists	18,0 (17,5)	
4.	office workers	25 (25,0)	
5.	technicians	55 (54,0)	
	Total:	397 (387,68)	

4. Financing

4.1 Total estimated cost of the project/LRIP subproject

The total cost estimate of the project (for the whole period, excluding salary).
The details are given in a separate table below.

35 900 k\$

4.2 Extra funding sources

Expected funding from partners/customers – a total estimate.

2 200 k\$

Project (LRIP subproject) Leader  Butenko A.V.

Date of submission of the project (LRIP subproject) to the Chief Scientific Secretary: _____

Date of decision of the laboratory's STC: 09.04.2024 document number: _____

Year of the project (LRIP subproject) start: _____

(for extended projects) – Project start year: 2011

Proposed schedule and resource request for the Project / LRIP subproject

Expenditures, resources, funding sources		Cost (thousands of US dollars)/ Resource requirements	Cost/Resources, distribution by years			
			1 st year	2 nd year	3 rd year	
	International cooperation	900	300	300	300	
	Materials	10500	3900	3300	3300	
	Equipment, Third-party company services	18500	7500	5500	5500	
	Commissioning	2100	780	660	660	
	R&D contracts with other research organizations	3500	1300	1100	1100	
	Software purchasing	400	150	150	100	
	Design/construction	-	-	-	-	
	Service costs (planned in case of direct project affiliation)	-	-	-	-	
Resources required	Standard hours					
		Accelerator	2900	800	900	1200
Sources of funding	JINR Budget	35900	13930	11010	10960	
	Extrafunding (supplementary estimates)	2200	2200	-		

Project (LRIP subproject) Leader

 Butenko A.V.

Laboratory Economist

 / JAZAPENKOVA K.A.

APPROVAL SHEET FOR PROJECT / LRIP SUBPROJECT

TITLE OF THE PROJECT/LRIP SUBPROJECT

SHORT DESIGNATION OF THE PROJECT / SUBPROJECT OF THE LRIP

PROJECT/LRIP SUBPROJECT CODE

THEME / LRIP CODE

NAME OF THE PROJECT/ LRIP SUBPROJECT LEADER

AGREED

JINR VICE-DIRECTOR


SIGNATURE

NAME

DATE

CHIEF SCIENTIFIC SECRETARY

SIGNATURE

NAME

DATE

CHIEF ENGINEER

SIGNATURE

NAME

DATE

LABORATORY DIRECTOR


SIGNATURE

Butenko A.V.
NAME

DATE

CHIEF LABORATORY ENGINEER


SIGNATURE

N. Aganov
NAME

11.04.2024
DATE

LABORATORY SCIENTIFIC SECRETARY


SIGNATURE

a. Chepur
NAME

11.04.2024
DATE

THEME / LRIP LEADER


SIGNATURE

NAME

DATE

PROJECT / LRIP SUBPROJECT LEADER


SIGNATURE

Butenko A.V.
NAME

DATE

Scientific leader I


SIGNATURE

Meinob21.H.
NAME

11.04.2024
DATE

APPROVED BY THE PAC

SIGNATURE

NAME

DATE

PROJECT REPORT

1. General information on the project / LRIP subproject

1.1. Scientific field

Large JINR Research Infrastructure

1.2. Title of the project / LRIP subproject

Nuclotron-NICA

1.3. Project (LRIP subproject) code

02-1-1065-1-2011/2023

1.4. Theme / LRIP code

02-1-1065-2007/2026

1.5. Actual duration of the project/ LRIP subproject

2011 - 2024

1.6. Project / LRIP subproject Leader(s)

A.V. Butenko

H.G. Khodzhibagiyev

Scientific leader: I.N. Meshkov

2. Scientific report

2.1. Annotation

The main goals of the Nuclotron-NICA project for the period of 2021 to 2024 have been:

- completion of the accelerator complex construction,
- carrying out commissioning works at the collider with the starting configuration of the equipment,
- completion of the collider construction in the basic configuration.

The main parts of the accelerator complex, which still need to be completed for the starting configuration are:

- an upgrade of Nuclotron beam injection and an addition of single turn extraction from Nuclotron (to the collider),
- Nuclotron-to-collider beam transport lines,
- completion of the collider in starting configuration,
- completion of experimental stations and beam lines to the targets of beam physics experiments and applied science, and the corresponding infrastructure,

- light ion linear accelerator LILAC,
- completion of the cryogenic complex upgrade.

Commissioning of the NICA injection complex was recently completed. The complex includes the heavy ion source KRION-6T, heavy ion linear accelerator HILAC, superconducting synchrotron-Booster, modernized Nuclotron and corresponding beam lines. BM@N and ARIADNA collaborations started experimental work.

Thus, the 1st stage of the mega-science project NICA was completed in 2023; i.e. the collider injection complex was commissioned, experimental research at the BM@N detector was started using the slow extracted Nuclotron beam with the planned project configuration.

The following main results are expected to the end of 2024:

- vacuum and cryo-magnetic tests of the collider,
- readiness for collider commissioning with circulating beams in 2025.

The delay from the project schedule was determined mainly by delays in the collider building construction, the delivery of equipment of the Nuclotron-to-Collider beam transport line and the light ion linac (LILAC).

2.2. A detailed scientific report

2.2.1. A description of the research undertaken and the results obtained.

In the period from 2021 to 2023 the following main results were obtained:

- Construction, assembly and test of the elements of the Booster fast extraction system and the Booster-Nuclotron beam transport line were completed (Fig. 1).



Fig. 1. Elements of the Booster-Nuclotron beam transport line during assembly.

- In the period from 06.09 to 23.09.2021 the second commissioning run was performed. Its main goal was a test of the fast beam extraction from the Booster and the Booster-to-Nuclotron beamline. During this run He^{2+}

ions from the plasma source and Fe^{14+} from the laser source were accelerated.

The following main works were complete:

- the residual gas density was estimated via measurements of the helium ion life-time during the beam circulation at injection energy. Average pressure of the residual gas of $4 \cdot 10^{-9}$ Pa was achieved. That is sufficient for heavy ion acceleration,
- the RF accelerating system was tuned. The Fe^{14+} ions were accelerated up to 578 MeV/u with change of the harmonic number at intermediate plateau of the magnetic field,
- electron cooling of the iron beam at the injection energy was demonstrated,
- accelerated iron beam was extracted from the Booster and transported through the beam line to the entrance of the Nuclotron (Fig. 2).



Fig. 2. Iron beam spot at the luminescent screen at the exit of the Booster-Nuclotron beam line.

- Modern power supply system for the extracted beam line magnets was installed and commissioned (Fig. 3).




Fig. 3. Power supply units for magnetic elements of the extracted beam lines.

- In the period from 06.01 to 01.04.2022 the third commissioning run was performed. Carbon ions from the laser source were accelerated to the energy of 3 GeV/u in the Nuclotron. The following main works were consequently accomplished:
 - cooling down and maintaining the operating temperature of both rings were performed for the first time at the NICA injection complex,

- ionstrippingstationlocated inside the Booster-to-Nuclotron transport line was commissioned,
- beam injection into the Nuclotron, acceleration and slow extraction with spill duration up to 6 s were tuned,
- stable operation of the complex during 24 days was supported. In addition to the commissioning of the injection complex the beam was delivered to the SRC experiment.

During the fourth commissioning run carried out from 20.09.22 to 03.02.2023 the collider injection complex was operated in the complete configuration: heavy ion source KRION-6T, HILAC, Booster and Nuclotron. Modernization of the vacuum system of the extracted beam lines was completed. The elements of new beam diagnostics system were tested. The argon and xenon ions were accelerated. The xenon beam at energy of 3.9 GeV/u was delivered to BM@N experiment and for support of ARIADNA collaboration program. Booster electron cooling system was tuned resulting in the cooling time closed to the design value (Fig. 4).




Fig. 4. Dependence of beam current on time for the xenon beam measured by the fast current transformer at the end of cooling cycle: without cooling – upper plot, with cooling – downplot. The cooling time is about 100 ms.

- Assembly of the equipment of the SOCHI, SIMBO and ISKRA stations dedicated to the applied research program was completed. At the SOCHI station the experimental program was started (Figs. 5, 6).




Fig. 5. 22 – 23 December of 2021 - test of the SOCHI station equipment with the carbon beam at the 3.2 MeV/u kinetic energy.



Fig. 6. January of 2024 – assembly of the SIMBO and ISKRA stations is completed.

- Preparation of the NICA collider systems for technological run scheduled for the end of 2024 is in the final stage.

Expected development of the NICA project in 2024:

1. The efforts will be aimed at further improvements of the HILAC, Booster and Nuclotron, as well as the existing beam transport lines in buildings 1 and 205. The major goal for the rest of year will be an assembly of the collider start configuration and the Nuclotron-Collider beam transport line in the building 1 and the new building 17 and their commissioning, as well as an assembly and commissioning of the fast extraction from Nuclotron, an assembly and commissioning of beam

injection and the beam extraction from the Collider to its beam dump. Further development of the existing infrastructure for applied research with heavy ion beams. Preparation for the acceleration complex run in 2025.

2. Preparation of the cryogenic complex for machine commissioning scheduled to start in the end of 2024. The upgrade of the cryogenic includes an addition of two Collider refrigerators in new building 17 and the nitrogen system. The latter will allow us to operate with the closed nitrogen cycle supporting cooling to the liquid nitrogen temperatures with much lower operating cost

2.2.2. A list of the main publications of the JINR authors, including associated personnel on the results of the project (list of bibliographical references).

During the period from 2021 to 2024 the JINR authors prepared 156 publications including

- 36 publications in scientific journals,
- 87 conference reports.

Main publications:

1. Yu.N. Filatov, A.M. Kondratenko, M.A. Kondratenko, V.V. Vorobyov, S.V. Vinogradov, E.D. Tsyplakov, A.V. Butenko, E.M. Syresin, S.A. Kostromin, Ya.S. Derbenev, Numerical modeling of a proton spin-flipping system in the spin transparency mode at an integer spin resonance in JINR Nuclotron, Journal of Instrumentation, ISSN:1748-0221, № P12039, 2021
2. Kostromin, S.Sidorin, A., Heavy ion collider NICA at JINR, Journal of Instrumentation; ISSN 1748-0221; v. 16(03); [12 p.], 2021.
3. Melnikov S.A., Meshkov I.N., Impedance Budget of the NICA Collider Ring, Physics of Particles and Nuclei Letters, ISSN:1547-4771, eISSN:1531-8567, Изд:МАИК Наука/Interperiodica, V. 19, 2022
4. Filatov G., Slivin A., Syresin E., Butenko A., Vorozhtsov A., Agapov A., Shipulin K., Kolesnikov S., Karpinskii V., Kuznetsov M., Kirov S., Sergeev A., Galimov A., Tikhomirov A., Tyulkin V., Letkin D., Leushin D., Tuzikov A. Progress on New Beam Lines Design and Construction for Applied Research at NICA // Phys. Part. Nucl. Lett. 2022. V. 19, No. 5. P. 513.
5. A.Yu. Grebentsov, O.I. Brovko, A.V. Butenko, et. al., Booster RF System First Beam Tests, the Joint Accelerator Conferences Website Publishing, JACoW-RuPAC2021-WEPS14, 2021.
6. M. Bazanov, A. V. Butenko, B. V. Golovenskiy, et. al., Light-Ion Linear Accelerator for the NICA Project, Physics of Particles and Nuclei Letters, 2020, Vol. 17, No. 4, pp. 481–487.
7. A.V. Butenko, O.I. Brovko, A.R. Galimov, E.V. Gorbachev, S.A. Kostromin, V.N. Karpinsky, I.N. Meshkov, V.A. Monchinskiy, A.O. Sidorin, E.M. Syresin, G.V. Trubnikov, A.V. Tuzikov, A.V. Philippov, H.G. Khodzhbagiyan, NICA Booster: a new-generation superconducting synchrotron, Uspekhi Fizicheskikh Nauk 193 (2) 206 - 224 (2023)

2.2.3. A complete list of publications (electronic annex).

2.2.4. List of talks given at international conferences and meetings (electronic annex).

2.3. Results of related activities

2.3.1. Research and education activities. List of defended dissertations.

On results of the project 7 masterdiplomawere preparedatMEPhI, SPbSU, IUD,

2 candidatethesis were defended:

A.V.Tuzikov, «Heavy ion beam injection into the NICA Booster», 16.02.2023

K.A.Levterov, «Formation of accelerated ion beams at heavy ion injector of the NICA complex», 2.03.2023

2.3.2. Awards and prizes.

JINR prizes:

2021 First prize“Construction of the NICA Booster”

2022 Firstprize“Creation of systems of ion beam transfer to the Booster and Nuclotron synchrotrons of the NICA accelerator facility”

VekslerprizeofRAS:

2024 «Multifunctionalheavyionacceleratorcomplex – injectoroftheNICAcollider»

3. Participating countries, scientific and educational organizations

Presented in the Topical plan 2024 at the pages 21 – 24

4. Analysis of planned vs actually used resources: manpower (including associated personnel), financial, IT, infrastructure

4.1 Manpower (actual at the time of reporting)

№№ n/a	Category of personnel	JINR staff, amount of FTE	JINR Associated Personnel, amount of FTE
1.	Research scientists	54 (50,8)	3 (3)
2.	engineers	245 (240,38)	
3.	specialists	18,0 (17,5)	
4.	office workers	25 (25,0)	
5.	technicians	55 (54,0)	
	Total:	397 (387,68)	

4.2 The actual estimated cost of the project/ LRIP subproject

Names of costs, resources, funding sources		Cost (thousands of US dollars) / Resource request
	International cooperation	3 900,0
	Materials	30 340,0
	Equipment, Third-party company services	113 511,0
	Commissioning	82,8
	R&D contracts with other research organizations	6 331,2
	Software purchasing	466,7
	Design/construction	192,5
	Service costs (<i>planned in case of direct project affiliation</i>)	
Resources required	Standard hours	
Sources of funding	JINR Budget	154 824,2
	Extrabudgeting (supplementary estimates)	61 410,1

5. Conclusion

During 2021-2024 I stage of the mega-science project NICA was realized:

- injection complex of the collider was created including heavy ion source KRION-6T, HILAC, Booster, Nuclotron,
- the program of fundamental and applied researches was started at fixed targets.

The commission works were not completed at the following elements of the accelerator complex:

- beam transport line from Nuclotron to collider,
- basic configuration of the collider equipment,
- light ion linear accelerator LILAC.

The delay from the project schedule was determined mainly by delays in the collider building construction, delivery of the equipment of the beam transport line from Nuclotron to collider and elements of the LILAC.

6. Proposed reviewers

B.Yu.Sharkov, G.D.Shirkov

Theme / LRIP Leader

 _____

" ____ " _____ 202_г.

Project leader (project code) / LRIP subproject

 | Butenko A.V.

" ____ " _____ 202_г.

Laboratory Economist

 | ЯЗАРЕНКОВА А.А.

" ____ " _____ 202_г.

ВЫПИСКА ИЗ ПРОТОКОЛА
заседания НТС ЛФВЭ
от 09 апреля 2024 года

Присутствовали на заседании 33 члена НТС из общего числа 40 членов НТС.

НТС ЛФВЭ заслушал отчет и рассмотрел предложение о продлении проекта **Нуклотрон-NICA** (02-1-1065-1-2011/2024) темы (02-1-1065-2007/2026) «Комплекс NICA: создание комплекса ускорителей, коллайдера и экспериментальных установок на встречных и выведенных пучках ионов для изучения плотной барионной материи, спиновой структуры нуклонов и легких ядер, проведения прикладных и инновационных работ». НТС решил одобрить отчет и рекомендовать ПКК по физике частиц продлить проект до конца 2027 года.

Рецензенты: Б.Ю.Шарков, Г.Д.Ширков

Председатель НТС ЛФВЭ



Е.А.Строковский

Ученый секретарь НТС ЛФВЭ



С.П.Мерц

ABSTRACT OF THE MINUTES
OF THE APRIL 09, 2024
VBLHEP STC MEETING

33 STC members were present at the meeting out of a total of 40 STC members.

VBLHEP STC heard the report and considered the proposal on continuation of the **Nuclotron-NICA** (02-1-1065-1-2011/2024) project within the framework of theme (02-1-1065-2007/2026) “NICA Complex: Design and Construction of the Complex of Accelerators, Collider and Physics Experimental Facilities at Extracted and Colliding Ion Beams Aimed as Studying Dense Baryonic Matter and Spin Structure of Nucleons and Light Ions, and at Carrying out Applied and Innovation Projects”. STC decided to endorse the report and to recommend that PAC for Particle Physics support continuation of the project until the end of 2027.

Referees: B.Yu.Sharkov, G.D.Shirkov

VBLHEP STC Chairman



E.A.Strokovsky

VBLHEP STC Scientific Secretary



S.P.Merts