

# Status

## and work plans

# at the BM@N setup

Piyadin S.M.

08.10.2024




# Content of the report


<b>A.</b>	<b>Sequence of assembly of detecting elements at the BM@N setup:</b>	
1.	Detector installation in <b>BM@N</b> experimental hall for <b>Xe</b> run.....	<b>3</b>
2.	<b>BM@N</b> experimental hall. Preparation for modernization of detectors.....	<b>4</b>
3.	Installation of <b>ScWall</b> detector.....	<b>5</b>
4.	Installation of 2 <b>CSC big</b> detectors .....	<b>6</b>
5.	Beam pipe upstream the <b>SP-41</b> . Trigger detectors.....	<b>7</b>
6.	Beam pipe upstream the <b>SP-41</b> . <b>Si Beam Tracker</b> detectors.....	<b>8</b>
7.	Beam pipe upstream the <b>SP-41</b> . Target Station.....	<b>9</b>
8.	<b>GEM</b> modernization .....	<b>10</b>
9.	Installation of 7 <b>GEM</b> detectors.....	<b>11</b>
10.	Installation of <b>Forward Si</b> detectors.....	<b>12</b>
11.	Installation <b>Si-station</b> base on <b>STS</b> modules .....	<b>13</b>
12.	<b>ToF400</b> modernization .....	<b>14</b>
13.	Installation of 2 new <b>ToF400</b> .....	<b>15</b>
14.	Installation of 2 <b>ToF400</b> & 4 <b>CSC</b> & aluminum beam pipe.....	<b>16</b>
15.	Installation timetable.....	<b>17</b>
<b>B.</b>	<b>New configuration elements in <b>BM@N</b> experimental hall:</b>	
1.	The location of new vacuum boxes to the target of the <b>BM@N</b> setup.....	<b>18</b>
2.	New configuration of vacuum boxes for profilometer.....	<b>19</b>
3.	New configuration of vacuum boxes for <b>BC0</b> , <b>BC1</b> , <b>BC2</b> & <b>VC</b> detectors.....	<b>20</b>
4.	New calculations of biological protection of the <b>BM@N</b> installation.....	<b>21-26</b>
	<b>Conclusion</b> .....	<b>27</b>



# Detector installation in BM@N experimental hall for Xe run




3D model of the entire experimental hall of BM@N



## Preparation for modernization of detectors


The following elements of the BM@N installation were removed after Run 8:

1. 4 detectors ToF400;
2. 4 detectors CSC 1x1m;
3. CSC 1,5x2m;
4. FD;
5. small Gem;
6. Aluminum beam pipe;
7. SiMD;
8. 8 planes forward Si;
9. 14 Gem;
10. Carbon beam pipe;
11. DCH1;
12. DCH2;
13. ScWall;
14. Target Station;
15. BC1;
16. BC2;
17. VC.



The following elements have not been deleted:

1. Barell;
2. ToF700;
3. BH;
4. FHcal.





# Installation of ScWall detector

The following mechanical support elements have been prepared:

1. Mechanical support materials: **Yes**
2. Supporting structure for mechanical support : **Yes**
3. Brackets for fastening the supporting structure : **Yes**
4. Mechanical Support Project: **Yes**
5. The detector is ready for installation: **Yes**

ScWall is completely installed in the experimental hall now




**Novozhilov S.  
&  
Martovitsky E.**



# Installation of 2 CSC big detectors


The following mechanical support elements have been prepared:




1. Mechanical support materials: **Yes**
2. Supporting structure for mechanical support : **Yes**
3. Brackets for fastening the supporting structure : **Yes**
4. Mechanical Support Project: **Yes**
5. The detector is ready for installation: **Yes**

2 CSC big are completely installed in the experimental hall now

**Novozhilov S.**  
&  
**Martovitsky E.**



# Beam pipe upstream the SP-41 Trigger detectors




The position of the trigger detectors in a complete vacuum beam pipe configuration


All elements counter **BC2**



Amplitude correlation from  
two PMTs **BC1** counter




Amplitude correlation from  
two PMTs **BC2** counter




**S.Sedykh** will talk in more detail about the operation of trigger detectors

# Beam pipe upstream the SP-41 Si Beam Tracker detectors



The position of the **Si** beam track counters in a complete vacuum beam pipe configuration




Correlations for **3xSi** beam track counters

**D.Chemezov** will talk in more detail about the operation of **Si** beam tracker detectors



# Beam pipe upstream the SP-41 Target Station



The position of the Target Station in a complete vacuum beam pipe configuration


## Target station with **pneumatic motors**:

3 target + 1 without target for evaluating background;


Drive: pneumatic motors;

Target elements: use with non-magnetic materials;

Target installation control: **KTIR0411S** optocoupler (4 pcs.).




Currently, the design of a target assembly made of heat-conducting materials in the same design is being discussed.




# GEM modernization


Divider old configuration




The board on the detector




Location of the old divider on the Gem detector



Divider new configuration



High voltage pin new configuration



High voltage pin old configuration








Photo of Gem repair

# Installation of 7 GEM detectors



1. Mechanical support : **Yes**
2. The detector is ready for installation: **Yes**




Only after installing all **GEM** we will be able to complete the installation of **CSC** and **TOF400**


We installed 7 bottom **GEM** detectors.

# Installation of Forward Si detectors




N.Zamyatin will talk in more detail about the operation of Si detectors





forward SI installed in BM@N



3D view of forward Si




# Installation of Si-station based on STS modules



A. Sheremetev will talk in more detail about the operation of Si-station


# ToF400 modernization

We decided to expand ToF400 acceptance.  
To do this we will have to change the detector boxes.



Box size -  $\sim 1,5 \times 1,8 \text{ m}^2$   
Material — aluminium  
Minimizing material budget near to beam axis



The aluminum box guides are currently fully manufactured



M. Rumyantsev will talk in more detail about the operation of ToF400.

Assembled detectors will be ready by 15 November 2024.


# Installation of 2 new ToF400



1. Mechanical support materials: **Yes**
2. Supporting structure for mechanical support : **Yes**
3. Brackets for fastening the supporting structure : **Yes**
4. Mechanical Support Project: **Yes**
5. The detector is ready for installation: **No (Modernization now)**


Mechanical support for new ToF400 modules installed in the experimental hall

# Installation of 2 ToF400 & 4 CSC & aluminum beam pipe




Kruglova I.

1. After installing all GEM detectors, 2 new ToF400 will be installed.
2. The next stage will be the installation of 4 CSC 1x1 m.




Kruglova I.



We will be able to install the last 4 CSC only after the 2 ToF400 detectors are fully installed.



# Installation timetable




The table is divided into 3 zones.

In zone 3, work can be carried out in parallel.

But work on installing TOF 400 and GEM can only be carried out one after the other.


# The location of new vacuum boxes to the target of the BM@N setup



**Box for profilometer size 128x128mm**

The contract for the production of this box has already been drawn up.

**box for scintillation detector**



**Box for profilometer size 200x200mm**

# New configuration of vacuum boxes for profilometer

Novozhilov S.  
&  
Martovitsky E.




The vacuum box for the profilometer is installed between the quadrupole lenses **K200** and the **VKM** magnet.

Novozhilov S.  
&  
Martovitsky E.



The vacuum box for the profilometer is installed between the **SP-57** correction magnet and the **SP-41** analyzing magnet.


# New configuration of vacuum boxes for BC0, BC1, BC2 & VC detectors



Novozhilov S.  
&  
Martovitsky E.



Vacuum box for trigger detectors installed in front of the target station




Novozhilov S.  
&  
Martovitsky E.



At the moment, the beam pipe to the target is being adjusted taking into account the installation and new configuration of the vacuum boxes.

# New calculations of biological protection of the BM@N installation

Statistically significant calculations of neutron flux and equivalent radiation dose rate in selected areas of the BM@N installation for a gold beam with an energy of 3.8 AGeV for final selection of the beamstop configuration performed using supercomputer Govorun and packages FLUKA/v2021.2.9 and FLUKA/v2023.3.2.




# Different beam dump configurations



# Definition of axes for biological protection calculations of the BM@N setup

DoseEq bmn\_conf29n\_22\_plot2D\_ALL280\_XZ

Litvinenko E.




The **X** axis is directed horizontally.


The **Z** axis is directed along the beam axis, but the origin of the axis coincides with the origin of the quadrupole lenses

# Distributions in the horizontal plane of the neutron flux at the beam pipe level



Conf12n  
neutron





Litvinenko E.



Conf29  
neutron




Conf29n  
neutron






# Distribution of equivalent dose rate ( $\mu\text{Sv}/\text{hour}$ ) in the CAVE zone



We observe that when using polyethylene in front of the beam stop, the neutron background inside the installation decreases.

# Distribution of equivalent dose rate ( $\mu\text{Sv}/\text{hour}$ ) in the PASSAGE zone




A decrease in the neutron background is also observed behind the wall of the beam stop.

# Conclusions

---

1. All work on the design and creation of mechanical supports was completed, taking into account the modernization of the external track system of the **BM@N** installation.
2. Installation of the central tracking system inside the **SP-41** magnet began after the completion of the process of upgrading the detectors themselves. The bottom GEM detectors have been installed.
3. **ScWall** & 2 big **CSC** installed in the experimental hall of the **BM@N** installation.
4. Mechanical support for 2 new **ToF400** & 4 **CSC** installed in the experimental hall.
5. New vacuum box elements for different detectors have been installed.



Work continues on upgrading the **BM@N** setup....



**THANK YOU  
FOR YOUR  
ATTENTION**

