

# ECal Status

Dubna April 2025

# Half sectors production


Produced and Tested about 1000+800 modules.  
530 more modules needed

40 Sectors assembled  
Out of 50 in the project

Production of last 530 modules started in the end of January  
Modules production rate Is limited by the production rate of WLS fiber  
Which is 6 km/month out of 60 km needed.

If production rate of WLS fibers will not be increased, in the end of august 45 sectors will be ready. 46 sectors will be ready for installation in the end of August.

Only in November sectors production may be completed.



Nbaskets  
ready

50

40

30

20

10

0

April

may

June

July

august

September

November

40

1920 Mod

45

2160 Mod


46

2208 Mod

?

50

2400 Mod



# Tests




- Cosmic muons tests
- Operation Stability tests with LED

1

**Half sectors (768 channels each) are studied on the operation stability by LED illuminating the WLS fibers through side glow fiber**  
**Signals deviation from the reference values was analyzed vs time**
























$A=2548$



$A=29429$

$$A_l/A_t=11,55$$



## **Conclusions:**

- **First 40 baskets of ECal are ready to be assembled to the MPD.**
- **Work is in progress to build 400 more modules increasing ECal coverage in the barrel region up to 100%.**
- **We are estimating 46 (92%) baskets will be ready to the end of august 2025. Unlikely more.**
- **Assembled halfsectors are under long term tests. Stability of ECal operation demonstrated on the level of few % for 768 channels.**

**Possibility to use cosmic muons for the calibration of the assembled ECal is demonstrated.**

- **ECal Slow Control and Stability Control software is under tests using assembled half sectors.**



**Thank you for the attention!**

