# Update on ECAL Construction

Andrei Semenov and MPD ECAL Group


D-060.1111.110 Модуль ECAL




#### Components

- Scintillator plates, 40x40x1.5 mm³
  Polypac company (Dubna) and Uniplast company (Vladimir)
  (Total amount ≈ 10 <sup>7</sup> plates; at the moment, more than 50% of plates are produced)
- Pressure plates and fiber bonding plate
   Polypac (Dubna) half of the full set is produced
- Lead plates, 40x40x0.3 mm³
   IHEP(Protvino) + ARMUL company (Mytishchi, Mockow region)
   (Total amount ≈ 10 <sup>7</sup> plates)
- Lead painting, layer thickness of 50μm
   Helios company (Dubna)
   (Pilot batches)








## Modules Gluing and Tests



Tests of scintillator light output and painted lead reflectivity





Universal tool for towers gluing




Tests on the bonding strength of the TiO<sub>2</sub>-based paint-glue

Eight Module
Types for
Projective
Geometry of
ECAL






1<sup>st</sup> Module Type



8<sup>th</sup> Module Type

### Prototype Modules Made in Protvino and China





The same production technology is used at all construction sites

#### Timelines for ECAL Modules Production

#### **Russia Contribution (25%):**

• IHEP (Protvino): 2 sectors in 10 months from now +2 sectors by the end of Summer 2020



• **Tenzor (Dubna)**: 1 sector in 6 months from now +2 sectors by the end of Summer 2020





#### **China Contribution (75%):**

 Tsinghua University (Beijing, China) + 3 other universities: we hope that financing will be started in 2019



#### Stand for ECAL Modules Calibration






- **√** Cosmic rays
- ✓ Test one load (12 modules) in 10-14 days
- √ 8 stands for 8 types of modules (with possibility of stend reconfiguration if needed)
- $\checkmark$  All modules test and calibration in about 1 year

#### **Production of Calibration Stands**





- **✓** Contract with Tenzor Company
- **✓** Engineering documentation is ready
- **✓** Sample stand is under production
- ✓ After the test of the sample stand, a tender for all stands production will be conducted






#### **MPD Power Frame**





- **✓** More than 6-m long and about 4.5 m in diameter
- **✓** Inner and outer mesh cylinders (carbon composite)
- **✓** 27 compartments for 54 half-sectors
- $\checkmark$  Total load of about 100 tons
- ✓ Maximal frame sagging should be less than 0.5 mm





#### CENTRAL RESEARCH INSTITUTE FOR SPECIAL MACHINERY

#### Joint Stock Company

Zavodskaya St., Khotkovo, Moscow Region, 141371, Russia Tel.: (495) **993-00-11**, fax: (49654) **3-82-94** e-mail: **tsniism@tsniism.ru** 



About | Management | Activity | Developments | Contact

#### **About the Institute**

The Central Research Institute for Special Machinery, Joint Stock Company (CRISM JSC) founded in 1963 in Khotkovo and reorganized into a joint stock company in 1993 is a leading Russian enterprise in design and production of structures on the basis of advanced polymer composite materials for rocket & space engineering, transport, power, petrochemical machinery and other industries.

- $\checkmark$  Extensive experience in design and production of big power frames
- ✓ Unique technologies
- **✓** Good history of collaboration with JINR (production of TPC cylinders for MPD)

#### Timelines for Containers and Frame

- ✓ Contracts with CRISM JSC to perform frame and container durability calculations and make 3D models are under negotiations
- ✓ Plan to have the engineering documentation by the end of the Summer 2019
- ✓ After that, the tender for production of the frame and the total amount of 54 containers will be conducted (hope to have the contract with CRISM JSC)
- ✓ Hope to have the frame and containers ready by the end of the


  Summer 2020

#### Installation of ECAL Electronics

Preliminary Concept from Arfis-Project Company




- $\checkmark$  One unit (box) carries 4 ADC boards (inside the box) and 16 preamplifier boards (below the box)
- **✓** The unit contains signal, power and cooling lines
- $\checkmark$  One installation unit for every 16 modules (viz., 3 unique boxes for every half-sector)
- ✓ Exact positioning of the preamplifier boards before the half-sector installation
- ✓ SiPMs positioning accuracy of about 0.2 mm
- $\checkmark$  Ability to extract and re-install electronics without dismounting the calorimeter




Installation step #1: The box with electronics (shown in green) is outside the half-sector.


All four ADC modules inside the box as well as 4 preamplifier boards (out of 16) below the box are shown.



Installation step #2: The box with electronics moves parallel to the beam direction, and it's half-way inside the half-sector.



Installation step #3: The box with electronics is completely inside the half-sector. SiPMs are still located far away the fiber's output windows.



Installation step #4: The box with electronics is lowered to the operation position. SiPMs have fixed gaps with the fiber's output windows.

# Timelines for Electronics Installation System

- ✓ Contract with Arfis-Project to produce engineering documentation is under negotiations
- ✓ Plan to have the documentation by the end of April 2019
- ✓ After that, the tender for production of the sample unit and the total amount of 162 units will be conducted

#### **Conclusions**

- **✓** We expect the MPD frame to be ready by the Fall 2020
- ✓ We plan to have 7 sectors (25%) of ECAL by the end of 2020
- ✓ We expect that the financing of China contribution (20 sectors or 75% of ECAL sectors) will be started in 2019