
ALICE DCS preparation for Run 3

Presenter: Alexander Kurepin (CERN)

On behalf of the ALICE Control Coordination team

Andre Augustinus (CERN), Peter Chochula (CERN), Ombretta Pinazza (CERN), Mateusz Lechman (CERN), Peter Matthew Bond (CERN), Kevin Cifuentes Salas (CERN), John Larry Lang (CERN)


The ALICE experiment is a heavy ion collision detector at the CERN LHC




- It is collaboration of 41 countries and more than 1800 scientists working on 19 detectors
- A large number of complex subsystems require supervision and control system (DCS)
- DCS assures safe and efficient operation of the detector
- 4 PB of raw physics data collected in 2017
- Search for rare events requires the increase of collision rate by factor 100
- ALICE detector needs to be modernized to cope with the new requirements


ALICE what's next

- 2019-2021 Long shutdown (LS2)
- Upgrade and installation of detectors
- Open new datacenter infrastructure, witch will host more than 1600 servers



)	Activity	Date
	Open L3 doors	14 Dec 2018
	TRD SM6 extraction	19 Dec 2018
	PHOS rework (incl. de-installation & re-installation)	7 Mar to 12 Dec 2019
	TRD rework	8 Apr to 30 Oct 2019
	TPC in SXL2	4 Mar 2019
	TPC in cleanroom	2 Apr 2019
	Move TPC to UX25	3 Feb 2020
	MFT installation	15 Apr 2020
	ITS installation	27 May 2020
	ITS & MFT commissioning time	8w
	ALICE global commissioning time	18w
	End of LS2	22 Feb 2021







0² new computing system


• New architecture

- read-out the data of all interactions
- compress data and online reconstruction
- common online-offline computing system
- 50kHz Pb-Pb event rate





Standard DCS Data Flow




What are the challenges?

- The DCS is in charge of ~1 000 000 parameters, scattered across:
 - >100 controls computers
 - ~1000 network attached devices
 - Hundreds of additional devices connected via many different busses
- The DCS receives the data on change, most of the devices do not use triggered readout
 - It is impossible to predict the time of arrival for a certain value
 - The update rate is typically slow, ranging from seconds to days
- The task is to:
 - Find and collect data
 - Assemble information for O²
 - Inject the DCS data into the O² data frames


The ADAPOS (Alice Datapoint Server) Architecture

- Each WINCC system will publish data to ADAPOS
- ADAPOS creates a process image a data structure containing:
 - DP alias
 - DP Type
 - Timestamped value
 - Quality flags
- ADAPOS TERMINAL will create a process image copy on the DCS FLP and keep it up to date
- ADAPOS is scalable and redundant architecture
 - More engines and terminals can be added for load balancing and redundancy

Redesigned DCS Data Flow



DCS in the context of O2 CONTROL data flow from DCS




DCS Interface to CRU – common readout unit



- Basic design principles:
 - The FLP is detector independent
 - All customization done at the DCS level
 - Same technologies and tools for all CRU users
 - There will be a single configuration path for the CRU configuration

The DCS place in the frontend chain




• We will run ALF on 270 servers and there will be 1 FRED per detector

 DETECTOR NEUTRAL LAYER ALF (Alice Low Level Frontend interface) provides communication interface to CRU firmware

- DETECTOR SPECIFIC LAYER FRED (Front End Device) runs on a dedicated server
- Receives commands from WinCC OA and forwards them to ALF
- Receives data from ALF and publish it to WinCC OA

ITS detector facts



- DCS data will arrive to CRU where it will be stripped off from the data stream
- DCS can access the CRU in order to write data (configuration) to frontend
- Data to read:
 - 24120*1 temperature values from chips
- Data to set:
 - 10 parameters/chip (241200 values in total)

Summary

- ALICE is preparing for long shutdown (LS2)
- Detector Control System assures safe work of detector
- DCS team developed ADAPOS architecture for communication with O² computing system
- To configure detector CRUs DCS will use ALFRED infrastructure
- Testing stand running in DCS laboratory
- ALICE DCS is now 14 years old and we do not need a major redesign of its core